

REPORT of SURVEY for REPAIRS.

No. 426 Survey held at London Date Sept 13 & Oct 27 1841
 in the Barque "John Craig" Master McLange
 Tonnage 376 Built at Shedden When built 1826
 By whom built _____ Owners C. Walton
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock _____

Original Survey, No. 33 Dated _____ Classified * E. 1

Port Newcastle, Lat. 54° 12' N, Long. 1° 52' W, Lon. 47° 29', 54° 46', 61° 75', 66° 02'

REPAIRS

At the present time Shifted several planks in the Sides & Water, two planks in the Buttock & lower stoke of Counter, the Timbers & Transoms where exposed all quite sound & good; Unbolted the Channels, doubled the sheer strakes with 2" American Oak. Spindles with cantyze fir & the webs & Blackstruts with American Elm (Oak in the wake of Chain bolts; rebolted the upper & lower deck shelf and an extra bolt in every wood lapping knee: Shipped caulked & lifepinned the bottom on abbot's felt: doubled the Deck with 1 1/2 inch cantyze fir & the waterway with 1 1/2 inch American Elm -

Present Condition of the

Decks <u>double</u>	Transoms <u>very good when seen</u>	Windlass _____
Upper Deck Beams & Fastenings <u>good & fair</u>	Timbers of the Frame <u>seen</u>	Capstan _____
Lower Deck Beams & Fastenings <u>fair</u>	Topsides _____	Pumps _____
Spirketting <u>good</u>	Wales <u>doubled</u>	Masts, Yards, &c. <u>good & efficient</u>
Plank Shears <u>"</u>	Counter _____	Sails _____
Waterways <u>doubled</u>	Plank & Treennails <u>good</u> (Outside to the Water's Edge)	Cables _____
Hatchway Coverings <u>good</u>	Rudder <u>"</u>	Anchors No. of _____
Breasthooks <u>good & fair</u>	Copper <u>new 1841</u>	Standing & Running Rigging _____

General Observations and Opinion.

This Ship is in a very good & efficient state, fit for the safe conveyance of any perishable goods too & from all parts of the world in my opinion should remain a classed

The Amount of Fee.....£ 2 : : is received by me,

Committee's Minute 20th October 1841

Character assigned First Class

Special 2-2-0

Wm. J. Clark
 Lloyd's Register
 Foundation