

REPORT of SURVEY for REPAIRS. 833

No. 421 Survey held at London Date Dec 17th & Jan 17th 1842
 on the Ship Wilmot Master Willa
 Tonnage 687 Built at Greenock When built 1836
 By whom built _____ Owners Sharpe
 Port belonging to Greenock Destined Voyage Sydney
 If Surveyed Afloat or in Dry Dock S. Katherine's dock

Original Survey, No. 1604 Dated _____ Classed R. 1

Port Liverpool, Lon. 3602, 5441, 5547, 8132.

REPAIRS

At the present time, Opened the ship at the
 Bidges agreeably to the rule Section found 16 timbers
 on the Starboard and 11 on the Larboard side, partially
 defective, ^{all} between the fore & main masts - the timber
 in the fore and after Cast bodies very sound & good
 took out a short plank and cut out some
 twisting pieces, under the lower deck clamps, to
 examine the timbers and found them in a good
 state ^{additional} fitted a pair of diagonal knee riding to the lower
 deck beams, and a pair of diagonal standards
 between decks, & a bulk clamp on the fore beam
 beam - 2nd Coppered at Colcutt in June last

Present Condition of the

Decks <u>Good</u>	Transoms <u>Good</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame in fair condition	Capstan <u>4</u>
Lower Deck Beams & Fastenings <u>Good</u>	Topsides <u>Good</u>	Pumps <u>4</u>
Spirkettling in a <u>Good</u> state	Wales <u>4</u>	Masts, Yards, &c. <u>4</u>
Plank Shears <u>4</u>	Counter <u>4</u>	Sails <u>4</u>
Waterways <u>4</u>	Plank & Treenails <u>4</u> (Outside to the Water's Edge)	Cables <u>4</u>
Hatchway Comings <u>4</u>	Rudder <u>4</u>	Anchors No. of <u>4</u>
Breasthooks <u>Good & fair</u>	Copper <u>4</u>	Standing & Running Rigging <u>4</u>

General Observations and Opinion,

This ship where seen is in a fair sound state
 fit to carry a dry perishable cargo, and in our
 opinion should be classed R. 1 S S 3 years from 1841

January 22, 1842. She was stripped, caulked and recoppered in
 Colcutt during 1841 about June 16th
 having been ashore

The Amount of Fee £ _____ is received by me,

Committee's Minute 21st Jan 1842

Character assigned R. 1 S. S. 3 1/2 1841

Special B. 3. 0



© 2019

Lloyd's Register
 Foundation

LONG12-0160