

# REPORT of SURVEY for REPAIRS.

No. 289 Survey held at London Date March & April 9 1842  
 on the Ship Morley Master Evans  
 Tonnage 492 Built at London When built 1811  
 By whom built Brent Owners Keith & Co  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock Blackwall Dock

Original Survey, No. 3171.328 Dated 5/11/42 1839 Classed F.1  
 Port London

## REPAIRS

at the present time new shear strakes and Pardeck  
 fore and aft all new upper Deck knee fastenings  
 Topmast doubled - New Fore castle Drifts  
 3 pair of Iron Rides in way of the Rigging &  
 3 pair Iron Hanging Standards in Hold - a quantity  
 of culing shifted from decks and in the Hold  
 new Deadwood knee and after Deadwood - generally  
 overhauled and put to rights -

The Timbers which were extensively exposed both  
 in the Hold & Fore Deck are in general good condition  
 the Rides are introduced to give additional security  
 in way of the Fore Rigging when the Timbers are not quite so good  
 as elsewhere -

Decks <u>Good fair order</u>	Transoms <u>Good</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>New</u>	Timbers of the Frame <u>Good fair order</u>	Capstan <u>"</u>
Lower Deck Beams & Fastenings <u>Overhauled</u>	Topsides <u>do</u>	Pumps <u>"</u>
Spirkelling <u>Good</u>	Wales <u>Good</u>	Masts, Yards, &c. <u>Overhauled</u>
Plank Shears <u>New</u>	Counter <u>"</u>	Sails <u>do</u>
Waterways <u>Good</u>	Plank and Treenails <u>"</u> (Outside to the Water's Edge)	Cables <u>Efficient</u>
Hatchway Comings <u>"</u>	Rudder <u>"</u>	Anchors No. of <u>3. 1. 1</u>
Breasthooks <u>"</u>	Copper <u>"</u>	Standing & Running Rigging <u>Overhauled</u>

General Observations and Opinion, The above Repairs have been done at the  
 recommendation & under the inspection of the  
 Surveyors of the Society - Their own opinion  
 fully efficient to remain as classed F.1  
 Special for Repair £5.5-

The Amount of Fee.....£ 2 : - : - is received by me, George Bayley

Committee's Minute 15th April 1842

Character assigned F.1 asterisk  
Record Repairs



© 2019

Lloyd's Register  
 Foundation

LON612-0437