

REPORT of SURVEY for REPAIRS.

No. 12 Survey held at London Date April 2nd to the 20th 1842
 on the Bk Ida Master Pumore
 Tonnage 459 Built at London When built 1814
 By whom built _____ Owners Smith & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Cubing & Yrangs Dry Dock & West India Dock

Original Survey, No. 2891, 3282 Dated 1841 Classed A, 1
4192, 4574, 4853, 6302, 6325, 7628, 8046,
 Port of London

REPAIRS This vessel has at the present time been surveyed by us specially for damage sustained in consequence grounding at Deptford on her last voyage and again off the West India Dock on the 1st Inst, and has had three iron riders over the Shelton extending to the heels of the second footboards over three floor-timber which were found to be sprung, one new aloft deck beam, one new middle deck beam, one new deck beam, four new oak lodging knees, & four iron knees - several sheets of copper & the sheathing stripped off to examine the state of the caulking which we found in very good condition, upper works caulked and a general examination -

May 4th The work nearly completed this morning. N.Y.

Present Condition of the

Decks <u>Good</u>	Transoms <u>Sound</u>	Windlass
Upper Deck Beams & Fastenings <u>good & firm</u>	Timbers of the Frame <u>sound & here seen</u>	Capstan
Lower Deck Beams & Fastenings <u>"</u>	Topsides <u>Good</u>	Pumps
Spirkettling <u>Good</u>	Wales <u>"</u>	Masts, Yards, &c. <u>Good</u>
Plank Shears <u>"</u>	Counter <u>"</u>	Sails <u>"</u>
Waterways <u>"</u>	Plank and Treenails <u>Good</u> (Outside to the Water's Edge)	Cables <u>Sufficient</u>
Hatchway Comings <u>"</u>	Rudder <u>"</u>	Anchors No. of <u>"</u>
Breasthooks <u>Sound</u>	Copper <u>"</u>	Standing & Running Rigging <u>"</u>

General Observations and Opinion, Several planks being shifted in the Ceiling have had an opportunity of examining the timbers which were found very sound, and from her general good appearance we are of opinion she is fit for the safe conveyance of my perishable cargoes & may continue as Repair A, 1

The Amount of Fee.....£ 2 : - : - is received by me, Wm. G. Black 3/6/42

Committee's Minute 3rd May 1842

Character assigned A, 1 used repairs

Wm. G. Black

Wm. G. Black
5 May 1842
Captain Captain



© 2019

Lloyd's Register
 Foundation

5050-719201