

REPORT of SURVEY for REPAIRS.

Restoration

8728

No. 180 Survey held at London Date Jan 28, Feb 17, 25 Mar 21 1842
 on the St Columbian Packet Master April 15 20 - day
 Tonnage 176 Built at London When built 1824
 By whom built Curling Young & Co Owners Benson & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Pateliff Dock

Original Survey, No. 1346 V 52 Dated 1836 Classed 1844
2536, 3060 - Cyl 378 - London 3706, 5339

Port London (excepting 40 ft)

REPAIRS At the present time the whole of the top side, stem to keel Plankstrakes
 waterways, Decks - a stake in the upper course on each side and a plank
 on each side ~~from the fore head~~ removed - The upper stowage
~~stowage~~ ^{length of 100 feet} and all the midship lengths of plank removed
 both outside and inside - New side stowage - all new top side
 (excepting 4 planks aboat) stem stowage Plankstrake, waterway, upper Deck
 St. Broom & Hold Broom fastenings - Stake in upper course fore
 and aft and all the lengthened part of English and African
 Oak or East India Oak - where required to be so - All defective
 timbers and plank removed that could be discovered.
 New Channel work - Head refitted

Present Condition of the
 Decks New 1842 Transoms Good Windlass Refitted
 Upper Deck Beams & Fastenings Good Timbers of the Frame Good Capstan _____
 Lower Deck Beams & Fastenings See 1841 Topsides New 1842 Pumps _____
 Spirketting New 1840 Wales New and the 1842 Masts, Yards, &c. _____
 Plank Sheers See 1840 Counter Good Sails _____
 Waterways See 1840 Plank & Treennails Good Cables _____
 Hatchway Comings Good Rudder Good Anchors No. of _____
 Breasthooks Good Copper _____ Standing & Running Rigging _____

General Observations and Opinion, The repairs to this vessel are done in a very
substantial and efficient manner and are sufficient
to restore her to the service for as long as the
Rules will admit - say 8 years

The Amount of Fee £ 2 - - is received by me, George Bayley

Committee's Minute 20th May 1842

Character assigned See 1841 for 8 years

Lloyd's Register
 Foundation