

ANNUAL SURVEYS.

8750

No. 1053 Survey held at London Date May 13th 1842
 on the 2c Alice Master W. Ward
 Tonnage 455 Built at Whitby When built 1813
 By whom built _____ Owners Chapman & Co
 Port belonging to London Destined Voyage London
 If Surveyed Afloat or in Dry Dock Plattin Dry Dock

Original Survey, No. 2842 Port of London Classified A.
5080, 5808, 8730

The Surveyor is required to state the present Condition of the

Decks <u>Good</u>	Transoms _____	Capstan _____
Upper Deck Beams & Fastenings <u>General inspection</u>	Timbers of the Frame _____	Pumps _____
Lower Deck Beams & Fastenings <u>Don't enter</u>	Topsides <u>Inspection at Whitt</u>	Masts, Yards, &c. _____
Spirkettling _____	Wales <u>Good</u>	Sails _____
Plank Shears <u>Don't enter</u>	Counter <u>Good</u>	Cables _____
Waterways <u>Don't enter</u>	Plank and Treennails <u>Good</u>	Anchors No. of _____
Hatchway Comings <u>Good</u>	Rudder <u>Good</u>	Standing & Running Rigging _____
Breasthooks <u>Don't enter</u>	Windlass <u>Good</u>	Copper <u>Don't enter</u>

General Observations and Opinion, There is a considerable movement on the Hold Beams, but
as required by the Instructions, at the Waterway down and Butts aloft. Ceiling is very
independent round fastenings. Recommended to shift Plank next waterway
and additionally bolt through the Waterway into the Deck - which will tend to
prevent the sagging of the Waterway beams. The repairs required to entitle this Ship
to remain as classed being 14 to 15 tons.
 Committee Minute 24th May 1842 advised that they should not be entered upon
but that she should lapse into the Class B
 Character assigned Reduced B as she will still be safe as a London Ship
George Bayley
N. W.

No. _____ Survey held at London Date May 13th 1842
 on the Ship Athenian Master Mann
 Tonnage 513 Built at Sunderland When built 1842
 By whom built J. Gale Owners Koulin
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Dowson Dry Dock

Original Survey, No. 1165 Port of Sunderland Classified 10 A1

The Surveyor is required to state the present Condition of the

Decks _____	Transoms _____	Capstan _____
Upper Deck Beams & Fastenings _____	Timbers of the Frame _____	Pumps _____
Lower Deck Beams & Fastenings _____	Topsides _____	Masts, Yards, &c. _____
Spirkettling _____	Wales _____	Sails _____
Plank Shears _____	Counter _____	Cables _____
Waterways _____	Plank and Treennails _____	Anchors No. of _____
Hatchway Comings _____	Rudder _____	Standing & Running Rigging _____
Breasthooks _____	Windlass _____	Copper _____

General Observations and Opinion, This Ship Standard. 3 additional Hold Beams Shaves
as required by the Instructions, put in and properly fastened as recommended Bottom
Sound and she is in good condition with Yellow Metal on plates 1842
This in my opinion entitles her to the Class A1
 Committee Minute 24th May 1842 George Bayley
 Character assigned 10 A1 Reduced B

May 11
12 Amount
2 Refrain
2 Amount
112



© 2019

Lloyd's Register
Foundation