

REPORT of SURVEY for REPAIRS.

8888

No. 468 Survey held at London Date May 25, 27, 28, 31 June 3 1842
on the Ship Childs Barrow Master W. H. Williams 13.16.25
Tonnage 402 Built at Exeter When built 1825
By whom built Sadler Bayley Owners W. H. Williams
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock Under the Dock

Original Survey, No. 382, 1758 Dated May 1841 Classed Star A1
3017, 3908, 3035, 6372, 7554. 1836
Port London

REPAIRS At the present time - New Wals of East India Lark - doubled from the keel to the deck with 2 1/2. East India Lark and American Elm properly treenailed and through bolts at the Lower Deck fastenings shifted - Broad Boards below the Lower Deck uplets and refitted and bolted through all - New Lower Counter several planks of the Ceiling shifted - Timbers good when exposed - New main keelson of East India Lark 18 x 15 - excepting the after piece which remains in - Caulked throughouts and Coppend to the Wals - Doubled on Selt -
The Wals were wormed - being nearly all original plank, it was thought best to remove them entirely -

Present Condition of the

Decks <u>Good but thin</u>	Transoms <u>Good</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>Good</u>	Capstan _____
Lower Deck Beams & Fastenings <u>Good 1842</u>	Topside <u>Good</u>	Pumps <u>Good</u>
Spirkettling <u>Good</u>	Wals <u>Good 2 1/2 Lark 5</u>	Masts, Yards, &c. <u>Good but thin</u>
Plank Shears <u>Good</u>	Counter <u>Good</u>	Sails <u>Good but thin</u>
Waterways <u>Good</u>	Plank & Treennails (Outside to the Water's Edge) <u>Good</u>	Cables <u>Good but thin</u>
Hatchway Comings <u>Good</u>	Rudder <u>Good</u>	Anchor No. of <u>3. 12</u>
Breasthooks <u>Good uplets</u>	Copper <u>1842</u>	Standing & Running Rigging <u>Good but thin</u>

General Observations and Opinion.

In my opinion this Ship is fit for the conveyance of dry and perishable cargoes to and from all parts of the world and, this ship to be in as good condition as when she was built.
A1

The Amount of Fee £ 2 is received by me, George Bayley
Committee's Minute 1st July 1842
Character assigned Star A1

Special £ 10.10. -