

Restoration 9253

REPORT of SURVEY for REPAIRS.

No. 217 Survey held at London Date Feb 5. 7 11. 14. 15. 16. 1842
 on the St. Hector Master E. W. Fox
 Tonnage 293 Built at Bristol When built 1824
 By whom built _____ Owners _____
 Port belonging to London Destined Voyage Jamaica
 If Surveyed Afloat or in Dry Dock Cling Dock

Original Survey, No. 1891, 2858 Dated _____ Classed 11th R.
 Port London 3368, 4267, 4865, 5888, 6702, 8042,

REPAIRS At the present time new waterways and stike out in the upper course all fore and aft on both sides - Plank up above the floor head on each side inside 2 New half Beams - new waterways - Thick stike in upper course sufficient to secure the doubling as for margin - Doubled thence up with six stikes of 2 1/2 all through treenailed and bonted to the bottom stipped - Caulked keel up over all and reappears as before -

In 1841 Quoining Keels Hawked - Spiketting forward, Wale to Counter Keelson from chain chest aft several planks shifted forward below the wale & P-taking forward between the new upper deck and the beam -

Upper course doubled & the bottom sheathed with inch Fir over Patent Gilt Iron

Present Condition of the

| | | |
|---|---|--|
| Decks <u>new 1841</u> | Transoms <u>Good</u> | Windlass <u>Good</u> |
| Upper Deck Beams & Fastenings <u>1035</u> | Timbers of the Frame <u>h</u> | Capstan _____ |
| Lower Deck Beams & Fastenings <u>1040</u> | Topsides <u>1036 28 35</u> | Pumps _____ |
| Spiketting <u>1041</u> | Wales <u>1841 29 30</u> | Masts, Yards, &c. <u>Good sufficient</u> |
| Plank Shears <u>1835</u> | Counter <u>1841</u> | Sails <u>Good</u> |
| Waterways <u>1842</u> | Plank & Treenails (Outside to the Water's Edge) <u>Good</u> | Cables <u>Good</u> |
| Hatchway Comings <u>Good</u> | Rudder <u>Good</u> | Anchors No. of <u>2</u> |
| Breasthooks <u>Good</u> | Copper <u>1842</u> | Standing & Running Rigging <u>Good</u> |

General Observations and Opinion, All parts where opened found to be sound and in good condition in our opinion the whole of the repairs of the Rule for restoration being now completed with this eligible to be restored for as long a period as the Rule will admit

The Amount of Fee.....£ 3 : - : - is received by me,

Committee's Minute 29th November 1842.

Character assigned Restored



© 2019

Lloyd's Register Foundation

LON 614-0338