

# ANNUAL SURVEYS.

9825

No. 8 Survey held at London Date 10<sup>th</sup> & 13<sup>th</sup> June 1843  
 on the Ship "Madagascar" Master Waller  
 Tonnage 835 Built at London When built 1838  
 By whom built Green Wigram & Co Owners R Green  
 Port belonging to London Destined Voyage Calcutta  
 If Surveyed Afloat or in Dry Dock East India Dock

Original Survey, No. 4693, 6444, 6913, 7566, 8749, Port of London Classed 12A1

The Surveyor is required to state the present Condition of the

Decks	<u>Good</u>	Transoms	<u>Good</u>	Capstan	<u>Good</u>
Upper Deck Beams & Fastenings	<u>Do</u>	Timbers of the Frame	<u>Not Seen</u>	Pumps	<u>Do</u>
Lower Deck Beams & Fastenings	<u>Do</u>	Topsides	<u>Good</u>	Masts, Yards, &c.	<u>Sufficient</u>
Spirkettling	<u>Do</u>	Wales	<u>Settle</u>	Sails	<u>Settle</u>
Plank Shears	<u>Do</u>	Counter	<u>Settle</u>	Cables	<u>Settle</u>
Waterways	<u>Do</u>	Plank and Treenails (Outside to the Water's Edge.)	<u>Settle</u>	Anchors No. of	<u>3 Bower &amp; Stream</u>
Hatchway Comings	<u>Do</u>	Rudder	<u>Settle</u>	Standing & Running Rigging	<u>Good</u>
Breasthooks	<u>Do</u>	Windlass	<u>Settle</u>	Copper	<u>New at Calcutta</u> <u>Last voyage Aug 1842</u>

General Observations and Opinion,  
as required by the Instructions,

This vessel during last voyage was onshore in the  
Calcutta River and was docked there where she had 14 Iron  
riders fitted up the hold also sister keelsons fitted on the ends  
of the short floor timbers fitted three every third timber with Copper bolts

Committee Minute 20<sup>th</sup> June 1843 Her bottom plank was thro bolted with 1 inch  
Character assigned 12 A 1 Copper bolts each strake three every third timber  
rec'd copy and her bottom Caulked Churned  
Copper sheathed. She is in efficient condition  
and may remain as Classed 12 A 1 Hitcher

No. 283 Survey held at London Date 3<sup>rd</sup> to 12<sup>th</sup> June 1843  
 on the Ship "Cowbitz" Master Bouchere  
 Tonnage 303 Built at London When built 1840  
 By whom built Green Wigram & Co Owners Hudson Bay Company  
 Port belonging to London Destined Voyage Wigram Dock  
 If Surveyed Afloat or in Dry Dock

Original Survey, No. 6604 Port of London Classed 12A1

The Surveyor is required to state the present Condition of the

Decks	<u>Good</u>	Transoms	<u>Good</u>	Capstan	<u>Good</u>
Upper Deck Beams & Fastenings		Timbers of the Frame		Pumps	<u>Good</u>
Lower Deck Beams & Fastenings		Topsides		Masts, Yards, &c.	<u>New Bower &amp; Stream</u> <u>Good</u>
Spirkettling		Wales		Sails	<u>Good</u>
Plank Shears		Counter		Cables	<u>Good</u>
Waterways		Plank and Treenails (Outside to the Water's Edge.)		Anchors No. of	<u>Good</u>
Hatchway Comings		Rudder		Standing & Running Rigging	<u>Good</u>
Breasthooks		Windlass		Copper	<u>New Copper June 1843</u>

General Observations and Opinion,  
as required by the Instructions,

at this time her bottom was stripped and  
the wood sheathing Caulked and Spiled  
and recoppered. She is in efficient  
condition and may remain  
as Classed 12 A 1 Hitcher

Committee Minute 20<sup>th</sup> June 1843  
Character assigned 12 A 1 as Classed Joseph H Hitcher  
rec'd copy