

# REPORT of SURVEY for REPAIRS.

9886

No. 12 Survey held at London Date 15<sup>th</sup> to the 25<sup>th</sup> June 1843  
 on the B. Rawlin Master Karris  
 Tonnage 348 Built at Chepstow When built 1819  
 By whom built \_\_\_\_\_ Owners Thompson & Co  
 Port belonging to London Destined Voyage Jamaica  
 If Surveyed Afloat or in Dry Dock Kings Dock

Original Survey, No. 890, 2020, Dated \_\_\_\_\_ Classed \* A 2  
3080, 3724, 4599, 6877, 8082, 9072,  
 Port London

REPAIRS at this time her Cutwater was taken down and  
 a New upper Piece of Stem and Apron and a new  
 Piece of the Head was fitted to her one <sup>fair</sup> hanging  
 Iron Knee has been fitted in the after hold and  
 three Pairs of hanging and one Staple Knee has  
 been fitted to the quarter deck beams Several of  
 the throat bolts of lower deck beams have been renewed  
 new Coamings have been fitted to the four hatch  
 The wales, topsides Counter and Waterway beams  
 have been Caulked

July a third Bower anchor has been recommended to be  
 put on board which the Owner has promised to do  
 August 16<sup>th</sup> 1843

*I have the paying 1. of 16 any*

Present Condition of the	Good	Transoms	Good	Windlass	Good
Decks	Sett	Timbers of the Frame	Not Seen	Capstan	Sett
Upper Deck Beams & Fastenings	Sett	Topsides	Good	Pumps	Sett
Lower Deck Beams & Fastenings	Sett	Wales	Sett	Masts, Yards, &c.	Sufficient
Spirkettling	Sett	Counter	Sett	Sails	Sett
Plank Shears	Sett	Plank and Treenails (Outside to the Water's Edge)	Sett	Cables	Sett
Waterways	Sett	Rudder	Sett	Anchors No. of	
Hatchway Comings	Sett	Copper	Yellow Metal	Standing & Running Rigging	Sufficient
Breasthooks	Sett				

General Observations and Opinion,  
 as she is fit for the <sup>safe</sup> <sup>dry & persuable</sup> <sup>to</sup> <sup>Good</sup> <sup>to</sup>  
 and from all Parts of the world she may  
 remain as Classed Joseph H. Hulse

The Amount of Fee.....£ \_\_\_\_\_ is received by me,  
 Committee's Minute 14<sup>th</sup> July 1843  
 Character assigned A. 2 - asterisk  
 Lloyd's Register Foundation  
 LON 615-0341