

REPORT of SURVEY for REPAIRS.

2905
J. P. Denny

No. 841 Survey held at London Date 28 April 3rd 15th May 1843
 on the Ship "Arab" Master John Sumner
 Tonnage 415 Built at Stockton When built 1840
 By whom built J. Irving Junr Owners J. Irving Junr
 Port belonging to Bristol Destined Voyage _____
 If Surveyed Afloat or in Dry Dock in Mr Weymans Dry Dock

Original Survey, No. 157 Dated _____ Classed S A 1

Port Stockton, Lyn 7524
 REPAIRS at this time the treenails were renewed on both quarters and along both bilges the bolts of the hanging knees and pointers were backed out & renewed. The Stern timbers & transoms were secured by a new transom & iron knees and new Middle Counter plank. The beam abaft the windlass was clamped and four ^(two pairs) new iron hanging knees fitted to the upper deck beams, and four pairs to the hold beams, and four pairs of hanging knees & standards fitted in the poop a new plank of poop deck fitted on both sides, the main piece of rudder hooped. The damage of Bulwarks, Cabins and other parts of the ship repaired, the vessel hung and caulked all over to the second seam of deck and recoppered on tarred paper

Present Condition of the					
Decks	<u>Good</u>	Transoms	<u>Good</u>	Windlass	<u>Good</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>Good</u>	Capstan	<u>Good</u>
Lower Deck Beams & Fastenings	<u>Good</u>	Topsides	<u>Good</u>	Pumps	<u>Good</u>
Spirkettling	<u>Good</u>	Wales	<u>Good</u>	Masts, Yards, &c.	<u>Sufficient</u>
Plank Shears	<u>Good</u>	Counter	<u>Good</u>	Sails	<u>Detto</u>
Waterways	<u>Good</u>	Plank & Treenails (Outside to the Water's Edge)	<u>Good</u>	Cables	<u>Detto</u>
Hatchway Comings	<u>Good</u>	Rudder	<u>Good</u>	Anchors No. of	<u>Detto</u>
Breasthooks	<u>Good</u>	Copper	<u>New in May 1843</u>	Standing & Running Rigging	<u>Detto</u>

General Observations and Opinion,
 as the vessel is now in efficient condition she may remain as classed
 Joseph H. Ritchie

The Amount of Fee.....£ 2 : : is received by me, J. P. Denny
 Committee's Minute 25th July 1843
 Character assigned S A 1 recopied
 J. P. Denny Rep^d 8