

REPORT of SURVEY for REPAIRS.

No. 452 on the Bark "Hoslin Castle" Master J. Sadler
Survey held at London Date 15th Nov 1843
Tonnage 450 Built at Bristol When built 1819
By whom built _____ Owners Sadler & Co
Port belonging to Plymouth Destined Voyage Algiers & Ancona
If Surveyed Afloat or in Dry Dock in Sweetings Dock
Last Survey, No. 9699 Classed V.A.

Port London

REPAIRS at present this vessel's upper works have been doubled 14 strakes down from the gunwale with 2 inch Amer Elm Plank with felt only under the three lower strakes the doubling has been fastened with an iron through bolt every 5 feet and a "dumple" in every timber - Her upper deck ~~ways~~ have also been doubled from the breast of fore castle to the front of poop with 6 inch Amer Elm on felt - She has also had an ^{inner} ~~inner~~ shelf yicks by 16" ~~boards~~ fitted under the hold beams bolted thro the new doubling and there has been seven pairs of iron riders fitted in each bilge and the hold ceiling has been repaired and partly renewed in the bows, the fast ports in the bow have been refamed and the head has had two new large chucks fitted bot

Present Condition of the			
Decks	<u>Much worn</u>	Transoms	<u>where seen Good</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>where seen Good</u>
Lower Deck Beams & Fastenings	<u>—</u>	Topsides	<u>Newly doubled</u>
Spirketting	<u>—</u>	Wales	<u>—</u>
Plank Shears	<u>—</u>	Counter	<u>Good</u>
Waterways	<u>Newly doubled</u>	Plank & Treenails (Outside to the Water's Edge)	<u>Not seen</u>
Hatchway Comings	<u>Good</u>	Rudder	<u>Good</u>
Breasthooks	<u>two new Iron Rings in hold</u>	Copper	<u>Wood sheathed on felt in 1830</u>
General Observations and Opinion,		Windlass	<u>Good</u>
		Capstan	<u>—</u>
		Pumps	<u>—</u>
		Masts, Yards, &c.	<u>Sufficient</u>
		Sails	<u>Settle</u>
		Cables	<u>Settle</u>
		Anchors No. of	<u>Settle</u>
		Standing & Running Rigging	<u>Settle</u>

In our opinion this Vessel is now fit for the Conveyance of dry & perishable Cargoes and may be restored to Class 1

The Amount of Fee.....£ 2 : — : — is received by me, Joseph H. Ritchie
Committee's Minute 28th November 1843
Character assigned Fit for service
Specimen