

17c Entry

10, 257

REPORT of SURVEY for REPAIRS.

No. 1546 Survey held at London Date Oct^r 18th to Nov 22 1843
 on the Steam Vessel Belfast Master _____
 Tonnage 146 Built at Belfast When built 1821
 By whom built _____ Owners Genl Steam Navigation Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock In's Dry Dock & Deptford Creek
 len. 33

Original Survey, No. 1546 Dated _____ Classed E. \ Ship omitted

Port London

REPAIRS

at the present time the cladding out from luff of bow aft 60 timbers shifted on the Starboard side and 49 on the Starboard side - All new upper pieces to Engine sleepers, midship doubling all shifted 2 new beams - Pair Pointers, Antech, & New to Counter, Transom, 6 pair Hanging knees 10 pair Iron Plate Riders two pair Long knee Riders - Caulked from keel up overall - The Main Deck new amidships from Engine Room - all the fastenings put through the doubling -

The inner surface of the Outside Planking in good condition of English Oak - The remaining part of the Frame in good fair condition - Has new Boilers & Engines refitted

Present Condition of the

Decks <u>Good</u>	Transoms <u>Good</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>new</u>	Timbers of the Frame <u>Good</u>	Capstan _____
Lower Deck Beams & Fastenings _____	Topsides <u>Good</u>	Pumps <u>Good</u>
Spirkettling <u>Good</u>	Wales <u>Good</u>	Masts, Yards, &c. <u>Good sufficient</u>
Plank Shears <u>Good</u>	Counter <u>Good</u>	Sails <u>see see</u>
Waterways <u>Good</u>	Plank and Treenails <u>Good</u> (Outside to the Water's Edge)	Cables _____
Hatchway Comings <u>Good</u>	Rudder <u>Good</u>	Anchors No. of _____
Breasthooks <u>Good</u>	Copper _____	Standing & Running Rigging _____

General Observations and Opinion, In my opinion this vessel is now fit for the
conveyance of dry and perishable cargoes to and
from all parts of the world eligible to be classed
E. with the asterisk


George Bayley

The Amount of Fee.....£ : 10 : - is received by me,

Committee's Minute 1st December 1843

Character assigned E. 1 asterisk

record repair



© 2019

Lloyd's Register
Foundation

LOW 616-0247