

REPORT of SURVEY for REPAIRS.

10,618
H

No. 204 Survey held at London Date April 21 to May 6 1844
 on the Bk Agnes Master J Mitcalf
 Tonnage 593 Built at New Brunswick When built 1839
 By whom built _____ Owners Vaughan & Co
 Port belonging to London Destined Voyage Honduras
 If Surveyed Afloat or in Dry Dock Nelson Dock

Last Survey, No. 4461 Classified 4 A.1

Port Liverpool

REPAIRS At the present time bottom stripped, and six planks shifted in the bottom on the larboard bow & five the starboard bow having been wormed all the iron bolts in the riders & hanging knees shifted with Yellow Metal being 202 bolts, also several of the butt bolts unwormed in the upper course with Yellow Metal, - a stake of the planking inside has been removed from stem to starboard on both sides above the turn of the bilge & found all the timbers in a sound state, the upper deck fastenings, waterways, spirketting plank shears, Hpsides, lower deck fastenings, wales, planking outside & inside, keonails, beams, & breasthooks are all in a good condition, Caulked from the keel to the upper part of the wales & sheathed with Yellow Metal over felt to the 14 feet mark -

Present Condition of the		
Decks <u>Good</u>	Transoms <u>Sound</u>	Windlass <u>Good</u>
Upper Deck Beams & Fastenings <u>4</u>	Timbers of the Frame <u>Sound where seen</u>	Capstan <u>"</u>
Lower Deck Beams & Fastenings <u>1</u>	Topsides <u>Good</u>	Pumps <u>"</u>
Spirketting <u>Good</u>	Wales <u>"</u>	Masts, Yards, &c. <u>Sound parts new</u>
Plank Shears <u>"</u>	Counter <u>"</u>	Sails <u>Well found</u>
Waterways <u>"</u>	Plank & Treennails (Outside to the Water's Edge) <u>"</u>	Cables <u>"</u>
Hatchway Comings <u>"</u>	Rudder <u>"</u>	Anchors No. of <u>3 Bower 1 Stem 2 Kedge</u>
Breasthooks <u>"</u>	XXX <u>Yellow Metal over felt 1844</u>	Standing & Running Rigging <u>Good</u>

General Observations and Opinion, I am of opinion this vessel is in a good efficient state for the safe conveyance of Dry & Perishable cargo and may be classed F.1 S.S. for four years

W. Wood

The Amount of Fee.....£ 3 : : is received by me,

Committee's Minute 10th May 1844

Character assigned F.1 S.S. 44-49

Special Survey £2.2.0

recoo refect



© 2019

Lloyd's Register Foundation

LON 617-0145