

REPORT of SURVEY for REPAIRS.

Change of Owners & Continuation

No. ³⁹⁶ Survey held at London Date 18 24th & 27th May 1844
 on the Barck "London" Master Jannerman
 Tonnage 239 Built at Munderland When built 1833
 By whom built _____ Owners Jannerman & Son
 Port belonging to Glasgow Destined Voyage Cape of Good Hope & Guano Islands
 If Surveyed Afloat or in Dry Dock Hatcliff Cross Dock

Last Survey, No. 9270

Classed 10 A1

Port London

REPAIRS

at present the bottom has been stripped and Caulked from
 Keel up - 500 Treenails have been Unrued in the walls and
 upper Courses - 6 Pairs of add^l iron Hanging Nails have
 been fitted to the hold beams - a new deadwood knee of
 sound second hand oak has been fitted to stern frame and
 an iron Crutch also - the bottom has been Sheathed with
 Yellow Metal on dry Paper - the upper and lower deck bolts
 the outside Planks thro' which they pass the waterways & beams
 the house timbers, Knight heads, breasthooks, & transoms the
 floors & Keelsons - the Planking outside from the tight water
 Mark upwards the Ceiling inside - the frame and inner
 surface of the outside planking where seen the deck and
 Coaming are sound & good The Keel straight and sheer
 unaltered

Present Condition of the

Decks	<u>Good</u>	Transoms	<u>Good</u>	Windlass	<u>Good</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>Good</u>	Capstan	<u>Good</u>
Lower Deck Beams & Fastenings	<u>Fairly New</u>	Topsides	<u>Good</u>	Pumps	<u>Good</u>
Spirkettling	<u>Caulked Good</u>	Wales	<u>Caulked Good</u>	Masts, Yards, &c.	<u>Sufficient</u>
Plank Shears	<u>Good</u>	Counter	<u>Good</u>	Sails	<u>Sette</u>
Waterways	<u>Good</u>	Plank and Treenails (Outside to the Water's Edge)	<u>Fairly New</u>	Cables	<u>Sette</u>
Hatchway Comings	<u>Good</u>	Rudder	<u>Sound & Fastened</u>	Anchors No. of	<u>Sette</u>
Breasthooks	<u>Good</u>	Copper	<u>Yellow Metal New in May 1844</u>	Standing & Running Rigging	<u>Sette</u>

General Observations and Opinion,

This Vessel is in efficient Condition and may
 be continued on the first class for as long a period
 as the Rules admit say 3 years from 1843 - 3 A1

Joseph White

The Amount of Fee.....£ 3 : - : - is received by me,

Committee's Minute

28 May 1843

Character assigned

Class A1 for 3 years

Lloyd's Register
 Foundation

LON 617-0230