

11260

REPORT of SURVEY for REPAIRS.

Change of Owners

Rec'd 2 Aug

No. 573 Survey held at London Date 2^d 20th Dec 1844
on the Ship "Spartan" Master W. Henry
Tonnage 364 Built at Chepstow When built 1825
By whom built _____ Owners Geo. Marshall
Port belonging to London Destined Voyage P^r Adelaide
If Surveyed Afloat or in Dry Dock in Gordon's Dock

Last Survey, No. 8441

Classed * A. 1

Port London

REPAIRS

at present from damage docked stripped hung Caulked
all up new false keel fitted and bottom sheathed with
yellow metal on paper where doubled and on woods felt
below the doubling to the keel — and as she was found
to be working slightly at the hold beams six pairs of
iron hanging knees have now been fitted to them — and
one new iron breast hook fitted in the tween decks — new
lower rudder bands fitted others overhauled and refastened

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>—</u>	Breasthooks and Stemson	<u>—</u>	Pumps	<u>—</u>
Comings	<u>—</u>	Transoms, Pointers, and Crutches	<u>—</u>	Boats	<u>—</u>
Upper Deck Beams & Fastenings	<u>—</u>	Timbers of the Frame	<u>—</u>	Masts, Yards, &c.	<u>Sufficient</u>
Lower Deck Beams & Fastenings	<u>new hung knees added — Good</u>	Keelsons	<u>—</u>	Sails	<u>—</u>
Planksheers	<u>Good</u>	Clamps and Shelves	<u>—</u>	Anchors No. of	<u>3 B 1st 2 K</u>
Sheerstrakes	<u>—</u>	Ceiling	<u>—</u>	Cables	<u>Sufficient</u>
Topsides	<u>doubling Caulked</u>	Rudder	<u>bands refastened</u>	Hawsers and Warps	<u>—</u>
Wales	<u>—</u>	Copper	<u>4 M new part on felt part on paper Dec^r 1844</u>	Standing & Running Rigging	<u>Overhauled</u>
Plank (Bottom) and Counter	<u>—</u>				

General Observations and Opinion,

This Vessel appears in very efficient Condition and
fit for the ^{safe} conveyance of dry and perishable Cargoes
to and from all parts of the world and may remain

The Amount of Fee.....£ 2 : — : — is received by me,

Classed * A. 1
Joseph H. Hatcher

Certificate (if required) : : :

Committee's Minute 7th Jan'y 1845

Character assigned A. 1 See entry
under 573