

for Restoration

REPORT of SURVEY for REPAIRS.

11289

Rec 10 Jan
and January 1845

No. 422 Survey held at London Date November & December 1844
 on the Ship "Tullock Castle" Master W. H. Partridge
 Tonnage 323 Built at London When built 1827
 By whom built - Owners Darwinson & Co
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock builings & young Dry Dock

Last Survey, No. 8261

Classed Exempted
Wants repair

Port London

REPAIRS

New upper piece of stem, Apron, upper part of Knight from the lower deck upwards, two new Breast Hooks, others retted, new half of wing transom, 121 new top timbers in the whole or parts including stations, poop and fore castle timbers, which forms in many instances top timbers also, 33 filling timbers, part new side counter timbers, 4 new upper deck beams and 3 new ends to others, 6 new wood lacing knees, new in and out bolts to the knees of both upper and lower deck, the latter of copper, new wales, Black Strakes, topsides, sheer strokes and plank sheers, of East India Tree, waterways of Red pine, small part of upper deck new, new main hatch coverings, new treenailed down to the Bilges, new Rudder, Stern post lengthened, all new Channels, Chain bolts, and

Present Condition of the and Channel Iron work, couched all over and sheathed with yellow metal upon copper
 Decks Treenails New to Bilges
 Waterways New main hatch Breasthooks and Stemson good
 Comings New main hatch Transoms, Pointers, and Crutches good
 Upper Deck Beams & Fastenings good Timbers of the Frame Very good
 Lower Deck Beams & Fastenings do Keelsons do do
 Plank sheers do Clamps and Shelves do do
 Sheerstrakes do Ceiling do do
 Topsides New E. I. Tree Rudder New post
 Wales do Copper 4 in 1845
 Plank (Bottom) and Counter do Windlass and Capstan overhauled & new
 Pumps good
 Boats do
 Masts, Yards, &c. do New Mainmast
 Sails 2 sails good
 Anchors No. of complete
 Cables do
 Hawser and Warps do
 Standing & Running Rigging New

General Observations and Opinion, She has been opened in conformity with the Society's Rules for Restoration and in her frame, and all other parts moves to be in a very sound and efficient condition, the repairs has been performed with the best materials and workmanship, and she is in our opinion entitled to be restored 8 years A1

The Amount of Fee.....£ 5 : - : - is received by me

Certificate (if required) - : 10 : -

Committee's Minute 17th Jan 1845

Character assigned Restored



© 2019

Lloyd's Register Foundation

LON 618 - 0305