

# REPORT of SURVEY for REPAIRS.

Recd 14 May

No. 11320 Survey held at London Date 25<sup>o</sup> 26<sup>a</sup> 30<sup>n</sup> april 1844  
 on the Barque "Teronia" Master Neil  
 Tonnage 210 Built at Dumbarton When built 1839  
 By whom built \_\_\_\_\_ Owners McLeod  
 Port belonging to Glasgow Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock in New Crane Dock

Last Survey, No. \_\_\_\_\_

Classed S A 1

Port \_\_\_\_\_

REPAIRS

at present the bottom has been stripped to repair damage  
 she has been hung in Shores, new <sup>4</sup>/<sub>5</sub> galn. Keel fitted, all the  
 treenails from the bely to the wales, from the fore part  
 of the fore Channel to the after part of the Main Channel  
 have been renewed, and some of the treenails in the topsides  
 that had been started were also renewed - The middle  
 piece of Main Keelson has been shifted - the fore Channel  
 has been refastened - the rudder overhauled & bands refitted  
 she has been Caulked all up, and bottom sheathed  
 with Yellow Metal on Paper -

Present Condition of the

|                               |             |  |   |                            |                   |
|-------------------------------|-------------|--|---|----------------------------|-------------------|
| Decks                         | <u>Good</u> | Transoms   | <u>Good</u>   | Windlass                   | <u>Good</u>       |
| Upper Deck Beams & Fastenings | <u>—</u>    | Timbers of the Frame                               | <u>—</u>  | Capstan                    | <u>—</u>          |
| Lower Deck Beams & Fastenings | <u>—</u>    | Topsides   | <u>—</u>  | Pumps                      | <u>—</u>          |
| Spirkettling                  | <u>—</u>    | Wales  | <u>—</u>  | Masts, Yards, &c.          | <u>Sufficient</u> |
| Plank Shears                  | <u>—</u>    | Counter  | <u>—</u>  | Sails                      | <u>—</u>          |
| Waterways                     | <u>—</u>    | Plank & Treenails<br>(Outside to the Water's Edge) | <u>—</u>  | Cables                     | <u>—</u>          |
| Hatchway Comings              | <u>—</u>    | Rudder   | <u>—</u>  | Anchors No. of             | <u>—</u>          |
| Breasthooks                   | <u>—</u>    | Copper   | <u>Yellow Metal<br/>on Paper new April<br/>1844</u> | Standing & Running Rigging | <u>—</u>          |

General Observations and Opinion,

This Vessel appears in efficient Condition and  
 in our opinion fit to remain as Classed

Joseph H. Hatcher

The Amount of Fee.....£ : : is received by me,

Committee's Minute \_\_\_\_\_ 18

Character assigned \_\_\_\_\_



© 2019

Lloyd's Register  
Foundation

LON 618-0334