

REPORT of SURVEY for REPAIRS.

Continuation

1263

No. 243 Survey held at London Date 23^d 24th June 1846
 on the "Sannet" Master Chalmers
 Tonnage 317 Built at Yarmouth When built 1834
 By whom built F Pustou Owners Scott & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock in New Crane Dock

Last Survey, No. 10911

Classed 12 A 1

Port London

REPAIRS

at Present the Midship lengths of upper Sheerstrake on both sides have been renewed of East India Teak Plank with all the upper deck bolts that pass thro' them new the timbers exposed were perfectly sound several of the lower deck bolts have been renewed of iron a new inner transom of iron has been fitted thro bolted with Copper one broken iron knee of lower deck taken down and repaired & replaced - The upper and lower deck bolts and the outside Planking thro which they pass the waterways and beams where seen the knee timbers, knight heads breasthooks and transoms the floors & Keelson the Planking outside from the Copper upwards the Ceiling inside the frame and inner surface of the outside Planking where

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>—</u>	Breasthooks and Stemson	<u>—</u>	Pumps	<u>—</u>
Comings	<u>—</u>	Transoms, Pointers, and Crutches	<u>—</u>	Boats	<u>—</u>
Upper Deck Beams & Fastenings	<u>—</u>	Timbers of the Frame	<u>—</u>	Masts, Yards, &c.	<u>Sufficient</u>
Lower Deck Beams & Fastenings	<u>—</u>	Keelsons	<u>—</u>	Sails	<u>—</u>
Planksheers	<u>—</u>	Clamps and Shelves	<u>—</u>	Anchors No. of	<u>30 12 1/2</u>
Sheerstrakes	<u>Scraped & bright</u>	Ceiling	<u>—</u>	Cables	<u>—</u>
Topsides	<u>—</u>	Rudder	<u>—</u>	Hawsers and Warps	<u>—</u>
Wales	<u>—</u>	Copper	<u>41 Smooth & Good</u>	Standing & Running Rigging	<u>—</u>
Plank (Bottom) and Counter	<u>—</u>				

General Observations and Opinion,

This Vessel is in very sound and efficient Condition and may be Continued on the first Class as long as the Rules admit say

The Amount of Fee.....£ 4 : — : — is received by me, John 1846. 4 yrs. A 1

Certificate (if required) _____

Committee's Minute _____

Character assigned _____

7th July 1846

Mr A 1 for 4 years



© 2019

Lloyd's Register Foundation

LON 621-0183

12638 *See*

*Seen the decks and Comings and the sheer and general
form of the Ship unaltered*

St. Helier



© 2019

Lloyd's Register
Foundation