

Continuation REPORT of SURVEY for REPAIRS.

No. 130 Survey held at London Date June 10th to 26th 1846
 on the B^t Derwent Master James M^cPherson
 Tonnage 346 Built at Sunderland When built 1835
 By whom built _____ Owners Heisk & Comp^{rs}
 Port belonging to London Destined Voyage Hobart Town
 If Surveyed Afloat or in Dry Dock In Mess^r Fletcher & Co^s Dry Dock

Last Survey, No. 1135 Classed 11 A 1
6 mo 45
 Port London

REPAIRS at the present time in complying with Rule for Continuation Section N^o 54. The whole of outside Plank from Gunwales to Lower part of Wales scaped bright, the Copper stripped off Bolts and Treennails driven out at various parts for examination.

The following are new viz One Breast Hook of Iron, a Crutch of Iron now introduced, Throat Bolts of Hold Beam Hanging Knees which were of Iron, replaced with Copper; the Throat Bolts of each Lodging Knee to d^o renewed; Throat and Lug Bolts to Upper Deck Hanging Knees replaced. Ship Caulked throughout and the Bottom resheathed with Copper upon Paper.

The Comings, Waterways, Plank sheer Inside and outside Planking, Bolts, Treennails, Beams, Knees, Flawse, Timbers, Knight heads, Breast hooks, Transoms, Floors, Keelson, Timbers of the Frame. These and general sum of the ship where they may be seen have been examined, and appear in good condition.

Present Condition of the

Decks	Treennails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper now new upon Paper	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

This Barque has now been "Specially Surveyed" by us in accordance with Rule for Continuation Section N^o 54, and we are of opinion that her present condition entitles her to be Continued A 1 for 4 years from 1846

The Amount of Fee £ 4 : : is received by me,

Certificate (if required) : 10 :

Committee's Minute 28 July 1846

Character assigned Cent 4 1/2 record Copper

Special on Continuation £ 3.30



© 2019

Lloyd's Register
Foundation

LON 621-0245