

# REPORT of SURVEY for REPAIRS.

12066

No. 45 Survey held at London Date 31 May 12 June 1846  
 on the Sch<sup>r</sup> King Alfred Master M Knill  
 Tonnage 159 Built at Corbe When built 1838  
 By whom built \_\_\_\_\_ Owners Knill & Co  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock in London Dock & Williams Dock

Last Survey, No. 11615

Classed 12 A1

Port London

REPAIRS

at present from having taken fire in the fore castle deck while in the London Dock - 15 Strakes of deck renewed on the Starboard side and 8 Strakes of new deck on the larboard side - The <sup>four</sup> foremost upper deck beams new of English oak - Foremost length of upper D<sup>o</sup> Shelf two fore hoods of Clamps and six fore hoods of Ceiling an additional iron breast hook fitted in the tween decks all new fore castle deck and bulkheads, birch lockers new full bitt and flippers of windlass bitts running knees refitted to new beams Copper stripped off both bows and the uncovered <sup>top</sup> Caulked & freshened with yellow metal - new Mast <sup>top</sup> Parlays fitted & refitted.

Present Condition of the

Decks	<u>Caulked</u> <u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Refitted</u>
Waterways	<u>Good</u>	Breasthooks and Stemson	<u>Good</u>	Pumps	<u>Good</u>
Comings	<u>Good</u>	Transoms, Pointers, and Crutches	<u>Good</u>	Boats	<u>Good</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>Good</u>	Masts, Yards, &c.	<u>Sufficient</u>
Lower Deck Beams & Fastenings	<u>Good</u>	Keelsons	<u>Good</u>	Sails	<u>Good</u>
Planksheers	<u>Good</u>	Clamps and Shelves	<u>Good</u>	Anchors No. of	<u>Good</u>
Sheerstrakes	<u>Good</u>	Ceiling	<u>Good</u>	Cables	<u>Good</u>
Topsides	<u>Good</u>	Rudder	<u>Good</u>	Hawsers and Warps	<u>Good</u>
Wales	<u>Good</u>	Copper	<u>55 Sheets new for</u> <u>rest good</u>	Standing & Running Rigging	<u>Good</u>
Plank (Bottom) and Counter	<u>Good</u>				

General Observations and Opinion,

*This Vessel is in most efficient Condition and may continue as Clashed*

The Amount of Fee.....£ 1 : - - is received by me, A. H. Ritchie

Certificate (if required) : 5 : - A. H. Ritchie

Committee's Minute 14th July 1846

Character assigned 12 A1 used up

Special Damage £ 4. 4. 0



© 2019

Lloyd's Register Foundation

LON 621-0249