

REPORT of SURVEY for REPAIRS.

No. 124 Survey held at London Date from 29 June till 2 July 1846
 on the Ship "Wellington" Master Henrick
 Tonnage 473 Built at Bombay When built 1800
 By whom built _____ Owners Evans & Co
 Port belonging to London Destined Voyage Madras
 If Surveyed Afloat or in Dry Dock in Hawks Dock

Last Survey, No. 11678 Classed *A 1

Port London
 REPAIRS at Present Copper stripped and wood sheathing removed from the lower part of the doubling of upper Courses (put on in 1842) and the doubling continued down to the bilges fastened with trenails. Copper dunnage and thro' bolts the ceiling in hold renewed and ships new lumber struts of Amer Elm 5" thick wrought and ships - three old wood hanging knees removed from hold beams on each side and three pairs of long iron knees fitted in their places - the keelson has been additionally bolted thro' very ^{apartate} floor timber - the two lower breast hooks have been rebolted with Copper. The old wood sheathing put on in 1842 remaining on from bilges down doubling Caulked & resheathed with yellow metal

Decks	<u>Good</u>	Trenails	<u>Not seen</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>Good</u>	Breasthooks and Stemon	<u>the lower one Copper bolted</u>	Pumps	<u>—</u>
Comings	<u>Good</u>	Transoms, Pointers, and Crutches	<u>Good</u>	Boats	<u>—</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>—</u>	Masts, Yards, &c.	<u>Sufficient</u>
Lower Deck Beams & Fastenings	<u>Partly new</u>	Keelsons	<u>additionally iron bolted</u>	Sails	<u>—</u>
Planksheers	<u>Good</u>	Clamps and Shelves	<u>Good</u>	Anchors No. of	<u>—</u>
Sheerstrakes	<u>—</u>	Ceiling	<u>Exposed</u>	Cables	<u>—</u>
Topsides	<u>—</u>	Rudder	<u>—</u>	Hawsers and Warps	<u>—</u>
Wales	<u>—</u>	Copper	<u>of Mr New July 1846</u>	Standing & Running Rigging	<u>—</u>
Plank (Bottom) and Counter	<u>doubly good</u>				

General Observations and Opinion,
 This Vessel is in our opinion fit for the safe conveyance of dry and perishable cargoes to & from all parts of the World, and may be continued as classed *A 1 with asterisk
 The Amount of Fee.....£ 2 : — : — is received by me,
 Certificate (if required) _____

Committee's Minute 4 August 1846
 Character assigned A 1
 Special attend £2. 2/6
 Lloyd's Register Foundation

2920-129 No7