

REPORT of SURVEY for REPAIRS.

No. 321 Survey held at London Date 21 Sep 1846
 on the Bk William & Alfred Master W Lawrence R Thomas
 Tonnage 338 Built at Hull When built 1811
 By whom built _____ Owners J Read
 Port belonging to London Destined Voyage Antigua
 If Surveyed Afloat or in Dry Dock in Limekiln Dock

Last Survey, No. 11396

Classed *AE 1

Port London

REPAIRS at present two lengths of upper sheerstrake amidships on each side renewed - one length of topsides new on each side all new decks round the pumps - the Wood and Copper Sheathing stripped off all the afterhoods of the bottom over transoms removed and three new middle beams fitted with new fashion timbers and two new lower futtocks of Cant timbers on each side pointers unbolted and lifted after lengths of hold ceiling renewed and many planks of ceiling shifted in the hold - bottom plank piece caulked and made good and felled and doubled with 2 1/2 Amer Elm Planks from the keel to the wales beams fastened and thro' bolted every 6 feet with Copper bolts and bottom covered off paper

Present Condition of the

Decks <u>Partly new Good</u>	Treenails <u>new in doubling</u>	Windlass and Capstan <u>Good</u>
Waterways <u>---</u>	Breasthooks and Stemson <u>Good</u>	Pumps <u>---</u>
Comings <u>---</u>	Transoms, Pointers, and Crutches <u>refitted</u>	Boats <u>---</u>
Upper Deck Beams & Fastenings <u>---</u>	Timbers of the Frame <u>good</u>	Masts, Yards, &c. <u>Sufficient</u>
Lower Deck Beams & Fastenings <u>---</u>	Keelsons <u>---</u>	Sails <u>Good</u>
Planksheers <u>---</u>	Clamps and Shells <u>---</u>	Anchors No. of <u>---</u>
Sheerstrakes <u>partly new</u>	Ceiling <u>refitted</u>	Cables <u>---</u>
Topsides <u>deroped</u>	Rudder <u>---</u>	Hawsers and Warps <u>Sufft</u>
Wales <u>bright</u>	Copper <u>new on paper</u>	Standing & Running Rigging <u>Sufficient</u>
Plank (Bottom) and Counter <u>---</u>		

General Observations and Opinion,

This Vessel is now in efficient Condition fit for the safe conveyance of dry and perishable Cargoes to & from all parts of the world and may be continued as

The Amount of Fee.....£ 2 : - : - is received by me, Classed *AE 1 J. H. Hatcher

Certificate (if required) : 10 : *

Committee's Minute 27th Oct 1846

Character assigned Special repairs £4 4 -

Special repairs £4 4 -



© 2019

Lloyd's Register Foundation

LON 621-0474