

REPORT of SURVEY for REPAIRS.

13088

No. 487 Survey held at London Date 12th Jan^y 1847
 on the Ship "Royal George" Master J Greaves
 Tonnage 486 Built at Bull When built 1820
 By whom built _____ Owners J Marshall
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock in Curbing off London Dock

Last Survey, No. 11864 Classed new R.
 Port London Rest 38 - 6 Yw. Cont 44 - 2 45

REPAIRS at present several planks of wales shifted above
 300 feet in all - timbers exposed sound and lower
 deck binding bolts that passed thro' them renewed
 six new and sound second hand lodging knee fitted
 to hold beams - three sound second hand african oak
 beams fitted to upper deck under bowsprit keel and
 windlass - putt butt beam in hold new and the hold
 beams before & abaft it clamped - all new poop deck
 and two new poop beams all new poop longitudinal timbers
 and plank sheers two new planks in counter - new fore
 - castle deck, beams and waterways - bottom shipped
 doubling caulked and keel sheathed with yellow metal
 P. J. 1847

Present Condition of the	Good	Treenails	Good	Windlass and Copstan	Unfitted
Decks	Good		Good		Unfitted
Waterways	Good	Breasthooks and Stenson	Good	Pumps	Good
Comings	Good	Transoms, Pointers, and Crutches	Good	Boats	Good
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	Good	Masts, Yards, &c.	Sufficient
Lower Deck Beams & Fastenings	Good	Keelsons	Good	Sails	Good
Plank sheers	Scraped	Clamps and Shelves	Good	Anchors No. of	3 B 1 C 1 K
Sheerstrakes	and	Ceiling	Good	Cables	Suff
Topsides	Caulked	Rudder	Good	Hawsers and Warps	Good
Wales	Good	Copper	Y Metal New	Standing & Running Rigging	Unfitted
Plank (Bottom) and Counter	Good		Jan ^y 1847		

General Observations and Opinion.

This Vessel is in efficient Condition and fit
 for the safe conveyance of dry and perishable
 cargoes to & from all parts of the World, and
 may be classed *A* with asterisk

The Amount of Fee £ 2 : - : - is received by me. H

Certificate (if required) : 10 : - H

Committee's Minute 15th Jan^y 1847

Character assigned 1st class



© 2019

Lloyd's Register
 Foundation

LON 622-0159

13088 *Lon*

Hulls and topsides scraped topsides flamed over
and Caulked - New lower gunwale fitted solid
to galleys - Windlass refitted - Ceiling repaired
Hull spars stepping generally overhauled New
for top mast rigging and backstays fitted

J. H. H. H.

W. H. H. H.



© 2019

Lloyd's Register
Foundation