

ANNUAL SURVEYS.

13230

No. 2987 Survey held at London Date March 5th 1847
 on the 13th Pilot Master Hall
 Tonnage 2005 Built at Chesham When built 1809
 By whom built Cooper & Co. Owners Cooper & Co.
 Port belonging to Gowes Destined Voyage In & out of Dry Dock
 If Surveyed Afloat or in Dry Dock In & out of Dry Dock

Last Survey, No. 2987 Port of Newcastle Classed A 1

The present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches <u>good for class</u>	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>when seen</u>	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons <u>d^o</u>	Sails
Planksheers	Clamps and Shelves <u>d^o</u>	Anchors No. of
Sheerstrakes	Ceiling <u>d^o</u>	Cables
Topsides	Rudder <u>d^o</u>	Hawsers and Warps
Wales	Copper <u>pt D/46</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion, Repairs at present. The defective Fore end of Main keel and lower part of Stem trimmed away and a Piece of sound second hand English Elm introduced forming the spoke and making good the keel and Stem 14 feet in length moulded 15 inches at the largest part all well secured with Bolts this keelson &c.

Committee Minute 19th March 1847 The Condition of the Ceiling between Decks & in the Hold, also of the Transoms being too much decayed for the present character. Recommended that she be reduced to B 1 for which we consider her eligible Ja Martin Certificate (if required)

No. 623 Survey held at London Date March 9th 1847
 on the Sc Stanhope Master Richards
 Tonnage 110 Built at Scilly When built 1843
 By whom built London Owners Hooton & Co
 Port belonging to London Destined Voyage Galatz
 If Surveyed Afloat or in Dry Dock On Crisp's Wharf

Last Survey, No. 13112 Port of London Classed 5 A 1

The present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches <u>good when seen</u>	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>d^o</u>	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons <u>d^o</u>	Sails
Planksheers	Clamps and Shelves <u>d^o</u>	Anchors No. of
Sheerstrakes	Ceiling <u>d^o</u>	Cables
Topsides	Rudder <u>d^o</u>	Hawsers and Warps
Wales	Copper <u>Metal new put in</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion, At the present time. The remainder of the y Metal Sheathing below the four upper Strakes put on in January last. Stripped off and renewed upon Paper; the Bottom Caulked in that space.

Committee Minute 19th March 1847 The appears in good condition. Remain as classed Ja Martin Certificate (if required)