

REPORT of SURVEY for REPAIRS.

13344

No. 14 Survey held at London Date April 7 to 20 1847
 in the B^e Vanguard Master Carmood
 Tonnage 301 Built at Yarmouth When built 1841
 By whom built 341 Owners Captain J C^e
 Port belonging to Yarmouth Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock Williams & S Shipway

Last Survey, No. 12342 Classed 12 A 1
 Port London 44

REPAIRS at the present time.

The following are new, Starboards, a Plank of Topside 34 Feet long. Lubboard, a Plank, in upper and one in Lower Sheer Strake each 20 Feet long, 3 Planks of Topside one in each Strake 34 Feet long: 4 Stantions, 10 Top Timbers, 15 Feet of Deck Clamp and 24 Feet of Planksheer of English and African Oaks chiefly the latter: a pair of Diagonal Iron Ribs fitted in After Hold, two pairs hanging knees under Cabin Deck, a Pair at the Break of Poop and the Fore part of Poop Trussed, also a Pair of Iron Slaps each 10 feet long to give shift to those knees at the Break.

The Fore and Main Masts new, also the Lower Rigging of the Fore Mast

Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways	} good	Breasthooks and Stenson	} good when seen	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	In good order and sufficient
Lower Deck Beams & Fastenings	d ⁿ when seen	Keelsons	d ⁿ	Sails	
Planksheers		Clamps and Shelves	d ⁿ	Anchors No. of	
Sheerstrakes	d ⁿ	Ceiling	d ⁿ	Cables	
Topsides	d ⁿ	Rudder	d ⁿ	Hawsers and Warps	
Wales	d ⁿ	Copper of Metal 46	d ⁿ	Standing & Running Rigging	
Plank (Bottom) and Counter	d ⁿ				

General Observations and Opinion,

This Ship is in good condition entitled to remain as Classed A 1

The Amount of Fee.....£ 2 : — : — is received by me, J A Martin

Certificate (if required) : :

Committee's Minute 30th April 1847

Character assigned 12 A 1

Special Survey in 1846 £ 2. 2. 11
 2/6/47



© 2019

Lloyd's Register Foundation
 LON 622-0426