

REPORT of SURVEY for REPAIRS.

No. 243 Survey held at London Date 22 May 1847
 on the Ship "Sannett" Master W. Chalmers
 Tonnage 37 Built at Yarmouth When built 1834
 By whom built F. Preston Owners Scott & Co
 Port belonging to London Destined Voyage Mauritius
 If Surveyed Afloat or in Dry Dock in Lime Kiln Dock

Last Survey, No. 12638 Classed 1846 Coal 4/1

Port London
 REPAIRS at present from damage bottom stripped hung in
 shores. Caulked to the wales and bottom. Rethatched
 with yellow metal on felt above and on paper below
 and bot from damage - all the treenails renewed
 from the garboard strake to the keel (6500 new)
 new hog keelson under main ship new hold pillars
 new garboard quarter timber part new Boughton
 tail and 1 Boughton timber amidships on starboard
 side

Present Condition of the

Decks <u>Good</u>	Treenails <u>new from wales down</u>	Windlass and Capstan <u>Good</u>
Waterways <u>Good</u>	Breasthooks and Stemson <u>Good</u>	Pumps <u>Good</u>
Comings <u>Good</u>	Transoms, Pointers, and Crutches <u>Good</u>	Boats <u>Good</u>
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>Good</u>	Masts, Yards, &c. <u>Sufficient</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons <u>new hog amidships</u>	Sails <u>Good</u>
Planksheers <u>Caulked</u>	Clamps and Shells <u>Good</u>	Anchors No. of <u>Good</u>
Sheerstrakes <u>Good</u>	Ceiling <u>Good</u>	Cables <u>Good</u>
Topsides <u>Good</u>	Rudder <u>Good</u>	Hawsers and Warps <u>Good</u>
Wales <u>Good</u>	Copper <u>At M new on felt below</u>	Standing & Running Rigging <u>Good</u>
Plank (Bottom) and Counter <u>Good</u>		

General Observations and Opinion, May 1847

This Report is in official Condition &
 may remain as Clipped S. H. Ritchie

The Amount of Fee.....£..... is received by me,
 Certificate (if required) : :
 Committee's Minute 11th June 1847
 Character assigned Out 4.1.47
Special damage £3.3