

REPORT of SURVEY for REPAIRS.

1347

No 84

No. 1067 Survey held at London Date June 24 to July 1847
 on the Brig "Agnes" Master J. Thompson
 Tonnage 251 Built at Sunderland When built 1840
 By whom built _____ Owners R. Henderson
 Port belonging to Liverpool Destined Voyage North Sea
 If Surveyed Afloat or in Dry Dock In Fore of aft Dry Dock, Brunswick

Last Survey, No. 1067 Classed 10 A 1
 Port Bristol 2nd 46

REPAIRS at the present time. From damage by accident. By the whole of main keel and the Gripe new, the Yellow Metal Sheathing stripped off and removed upon Fall. Caulked from upper part of Wales to keel, two Planks of Ceiling at the Lael. Bridge to examine timbers, the same Planks replaced and additionally the Bolts; several started Treennails renewed.

Do from decay. A new Stems on knee extending well upon the Main Keelson, the defective part of the latter cut away and made good by the former, the two lower Breast Hoops in way of Stems on taken off and refitted, and a new Fore Piece of Main Keelson

Decks _____	Treennails _____	Windlass and Capstan _____
Waterways } <u>good</u>	Breasthooks and Stems on } _____	Pumps _____
Comings _____	Transoms, Pointers, and Crutches } <u>good when seen</u>	Boats _____
Upper Deck Beams & Fastenings } _____	Timbers of the Frame _____	Masts, Yards, &c. } <u>In good order</u>
Lower Deck Beams & Fastenings } <u>decreased</u>	Keelsons _____	Sails _____
Planksterns _____	Clamps and Shelves _____	Anchors No. of _____
Sicestrakes _____	Ceiling _____	Cables _____
Topsoles _____	Rudder _____	Hawsers and Warps _____
Wales _____	Copper Yellow Metal } <u>d.</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter _____	on Fall now new } _____	

General Observations and Opinion.
We are of opinion that this Brig is now in good condition, eligible to remain as Classed A 1

The Amount of Fee £ 1 : - : - is received by me, J. A. Martin
 Certificate (if required) : 10 : - : -
 Committee's Minute 4th July 1847
 Character assigned 10 A 1
 Special attendance £ 4 10 0
 on Damage _____