

# REPORT of SURVEY for REPAIRS.

13507

No. 72 Survey held at London Date July 2 to 9  
 on the Ship "Candahar" Master Sam Goss  
 Tonnage 566 Built at Shields When built 1841  
 By whom built — Owners A. Ridley  
 Port belonging to London Destined Voyage Madras  
 If Surveyed Afloat or in Dry Dock In Mess "Censons" Jan's Dry Dock

Last Survey, No. 13414 Classed A1  
 Port London

REPAIRS at the present time. Of damage by lying on Demerara Bar  
The Yellow Metal Sheathing stripped off and renewed upon both  
a pair of Kins Plates to secure heel of stern Post and keel. four Pairs  
of Staple Standards then up & down 130 lbs in Lower Deck Beam ends  
renewed. the Ship hung in Shores and Caulked from Wale to keel.

Is not of Damage by accident. The underside of main keel  
straightened by trimming off at Fore end and adding a Sole Piece  
at the hooped part. The Lower Timbers to Quarter Gallies taken off  
and four After Heads of Topside Stair and three on the Deck side renewed.  
The decayed fore part of Fore mast Piece of main keelson cut away  
and a substantial Piece of keelson introduced upon it extending upon  
former part of Apron under Fore Mast & 37 feet long of English Oak, and up to 21 feet long  
of the old coping Forward repaired; Caulked from Wale upwards

Decks	Treenails	Windlass and Capstan
Waterways } <u>good</u>	Breasthooks and Stenson } <u>good otherwise</u>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. } <u>In good order</u>
Lower Deck Beams & Fastenings } <u>discontinued</u>	Keelsons } <u>d.</u>	Sails } <u>adequate sufficient</u>
Plankishers	Clamps and Shells } <u>d.</u>	Anchors No. of
Sheerstrakes } <u>d.</u>	Ceiling } <u>d.</u>	Cables
Top-sides } <u>d.</u>	Rudder } <u>d.</u>	Hawsers and Warps
Wales } <u>d.</u>	Copper } <u>Metal now new upon</u>	Standing & Running Rigging
Plank (Bottom) and Counter } <u>d.</u>		

General Observations and Opinion,

We are of opinion that this Ship is now in  
good condition eligible to remain as Classed A1

The Amount of Fee..... 2 3 : - : - is received by me,

Certificate (if required) : 10 : -

Committee's Minute

Character assigned

Special on Damage &c £4-14-0

Lloyd's Register  
 Foundation