

REPORT of SURVEY for REPAIRS.

No. 384 Survey held at London Date July 7th to 17th 1847
 on the 13th Mary Master Grant
 Tonnage 443 Built at Shumland When built 1842
 By whom built 543 Owners Boulcott
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock In Mess Green's Dry Dock

Last Survey, No. 12312 Classed 9 A 1

Port London

REPAIRS now done of damage by being on Shore at Trincomalee.

The Yellow Metal Sheathing stripped off and renewed upon Felt, hung in Shores and Caulked from lower part of Masts to Keel. The lower after part of Rudder rounded off where twisted and its hangings secured: two Bidge Planks 32 ft 3 in long, 3rd replaced with new, and four other Planks repaired by piecing on the Larboard side, being chafed and worn.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>good</u>	Breasthooks and Stemson } <u>good & substantial</u>	Pumps
Comings	Transoms, Pointers, and Caulks	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. } <u>In good order and sufficient</u>
Lower Deck Beams & Fastenings } <u>abundant</u>	Keelsons } <u>d.</u>	Sails
Plank sheers	Clamps and Shelves } <u>d.</u>	Anchors No. of
Sheerstrakes } <u>d.</u>	Ceiling } <u>d.</u>	Cables
Topsides } <u>d.</u>	Rudder } <u>d.</u>	Hawsers and Warps
Wales } <u>d.</u>	Copper } <u>Yellow Metal now new upon Felt</u>	Standing & Running Rigging
Plank (Bottom) and Counter } <u>d.</u>		

General Observations and Opinion,

This Barque is now in good condition eligible to remain as Classed A 1

The Amount of Fee £ 2 : : is received by me, Lloyd's Register

Certificate (if required)

Committee's Minute 17 August 1847

Character assigned 9 A 1

Special Damage £ 4. 0. 0

Repaired & Dams up

LON623-0218