

REPORT of SURVEY for REPAIRS.

1254

No. 118 Survey held at London Date May 26th to June 17th 1847
 on the Se^r "Oriental" Master Christmas
 Tonnage 204 Built at Yarmouth When built 1841
 By whom built _____ Owners Captain J. C.
 Port belonging to Yarmouth Destined Voyage Mediterranean
 If Surveyed Afloat or in Dry Dock In Williams & Son's Dry Dock

Last Survey, No. 2909 Classed 12 A 1
 Port Swampool 45

REPAIRS at the present time. On the Starb^d side three Planks in midship of two Sheerstrakes, each 27 feet long, replaced with African Oak, also one Plank in upper Sheer Stakes Look^g 38 feet 4 1/2 feet of Planks here on each side removed with African Oak, and 55 feet of Deck Waterway 11 by 6 Red Pine on each side, and the Strake of Deck next it removed, the Bolts in Sheerstrakes and Waterway in way of d^o all properly replaced.

The Yellow Metal Sheathing stripped off, Caulked from second Seam of Deck next the Waterway down outside to keel and the Bottom re-sheathed with Yellow Metal upon the bare Plank


Present Condition of the

Decks _____	Treenails _____	Windlass and Capstan _____
Waterways } <u>good</u>	Breasthooks and Stenson } <u>good</u>	Pumps _____
Comings _____	Transoms, Pointers, and Cruisers } <u>good</u>	Boats _____
Upper Deck Beams & Fastenings } <u>good</u>	Timbers of the Frame _____	Masts, Yards, &c. } <u>In good order</u>
Lower Deck Beams & Fastenings } <u>good</u>	Keelsons _____	Sails _____
Planksheers _____	Clamps and Shelves _____	Anchors No. of _____
Sheerstrakes _____	Ceiling _____	Cables _____
Topsides _____	Rudder _____	Hawsers and Warps _____
Wales _____	_____ } <u>Yellow metal new</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter _____		

General Observations and Opinion.

This Schooner now appears to be in good condition and entitled to remain as Classed A 1

The Amount of Fee £ 1 : : : is received by me J. S. Martin
 Certificate (if required) : : :
 Committee's Minute 17th August 1847
 Character assigned 12 A 1 12 A 1
 Special attendance £ 1-1-0 pp



7-04623-019