

REPORT of SURVEY for REPAIRS.

No. 215 Survey held at London Date July 14 to 20 1847
 on the 13th "Clara" Master Adamson
 Tonnage 296 Built at Barkly When built 1819
 By whom built Owners G. J. Young
 Port belonging to London Destined Voyage
 If Surveyed Afloat or in Dry Dock In Mess^r Young's Yard, Bay St.

Last Survey, No. 12376 Classed X^A 1
46

Port London

REPAIRS now done, of damage by Collision with another vessel at Monte Video also by stress of weather in her passage home. four Planks of Tapside on the Starb^d Bow new: the whole of the Treennails in Starb^d Tapside and most of them on the Larb^d side of it renewed a new Wing Transom where Starb^d a pair of new Knees to the Transom across Stern Timbers also a pair of Staple Standards of Iron introduced to the after Deck Beam and upon the Wing Transom, a pair of Iron Hanging Knees to Hold Beam at Main Hatchway and Caulked Girth Wale upwards to second beam of Deck next the Waterway.

Not of damage by accident. The Ceiling between Decks and the Hold Ceiling damaged to upper edge of 15.10.10 Strakes dubbed over additionally fastened and repaired. The bottoming Hold Ceiling is now in misship to 140 feet Starb^d and 100 feet Larb^d. The after Piece of False Keel new

Present Condition of the

Decks	Treenails <u>fast new</u>	Windlass and Capstan
Waterways	Breasthooks and Stimson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons <u>not really seen for Ballast</u>	Sails
Plank sheers	Clamps and Shells	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

We are of opinion that this Barque is now fit for the safe conveyance of dry and perishable Cargoes to and from all parts of the world, and may be allowed to remain as Classed X^A 1

The Amount of Fee.....£ 1 : : is received by me.

Certificate (if required) : :

Committee's Minute 11th Dec 1847

Character assigned 11th Dec 1847

Special on damage £3-3-0 20P cccd up

LONG-5336047

© 2019

Lloyd's Register Foundation