

REPORT of SURVEY for REPAIRS.

13842

No. 288

No. 630 on the 13th "Commodore" Survey held at London Date Oct 10th Nov 9th 1847
 Master R Mayle
 Tonnage 203 Built at Newport When built 1835
 By whom built _____ Owners Sa^r Shepherd
 Port belonging to London Destined Voyage Jamaica
 If Surveyed Afloat or in Dry Dock In Snooks' Dry Dock

Last Survey, No. 12959 Classed 12 A 1
 Port London 46

REPAIRS at the present time in complying with Special Survey for Continuation Rule Section No. 54. The outside Planking from Copper upwards scraped bright Iron Bolts and Treennails driven out at various parts for examination; 66 Feet of Sheer-Strake Stanch^o and the same quantity Larch^o renewed with East India Teak; 67 Feet of Topperside Stanch^o and the same quantity Larch^o abreast of raised Quarter Deck renewed with Danzig Fir; 36 Fillings Stanch^o and 24 Larch^o introduced between Top Timbers in way of the above new Planking; 40 feet of new Planks here on each side, and 10 feet of Waterway Stanch^o of East India Teak; 40 feet of Deck next Waterway on each side new. Four Pairs of Iron Hanging Knees added to Deck Beams, all Bolts in way of new Planking renewed, and the Topsides Caulked.

The Deck, Coamings, Deck and Hold Beam Bolts, Inside and outside Planking, Treennails, Plank sheer, Waterway, Beams, Knees, Breast Hooks, Transoms, and other parts of the Frame, all of which have been examined and are in good condition.

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Cratches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper Metal/100 d ^o	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,
 This Barque has now been specially Surveyed in accordance with Rule for Continuation Section No. 54, and we are of opinion that she is in good condition fit to be continued 12 for 4 years from 1847

The Amount of Fee £ 3 : - : - is received by me, J. A. Martin
 Certificate (if required) _____

Committee's Minute 16th Nov 1847
 Character assigned 1st A
 Special Fee on Continuation £ 3. 3. -

LON 624-0022

