

# REPORT of SURVEY for REPAIRS.

No. 340 Survey held at London Date Dec 24<sup>th</sup> 1848  
 on the Brig "Friends" Master Thos. Purdon  
 Tonnage 211 Built at Scarbro When built 1802  
 By whom built \_\_\_\_\_ Owners J. Chaters  
 Port belonging to London Destined Voyage Hartlepool &  
 If Surveyed Afloat or in Dry Dock in Gun Dock

Last Survey, No. 13170 Classed A. 1

Port Newcastle

REPAIRS at present Caulked from the keels up and wales doubled with 2" Amer Elm. Topsides doubled with 2" Amer Elm and the Sheerstrakes doubled with 2" Amer Oak all on felt and iron bolts a thro bolt every 5<sup>th</sup> timber. Counter doubled with 2 inch Amer Elm and stred plank sheathed with 1 1/2" Pine - new toffrail fitted - Channet straps refitted and rebolted thro doubling - a new waterway of 3x12 Dautype fir fitted on hole beams bolted thro new doubling. Rudder overhauled and wood sheathed - all new hardwood bulwarks round the bows - waterways and quarter deck Caulked. This Vessel is now doubled from keel to gun wale.

Present Condition of the

Decks <u>Good</u>	Treenails <u>apparently Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>Caulked</u>	Breasthooks and Stemson <u>—</u>	Pumps <u>—</u>
Comings <u>—</u>	Transoms, Pointers, and Crutches <u>—</u>	Boats <u>two</u>
Upper Deck Beams & Fastenings <u>—</u>	Timbers of the Frame <u>where seen good</u>	Masts, Yards, &c. <u>Sufficient</u>
Lower Deck Beams & Fastenings <u>—</u>	Keelsons <u>—</u>	Sails <u>1 1/2 shifts</u>
Planksheers <u>—</u>	Clamps and Shells <u>—</u>	Anchors No. of <u>3 1 1</u>
Sheerstrakes <u>Doubled</u>	Ceiling <u>—</u>	Cables <u>Sufficient</u>
Topsides <u>Do</u>	Rudder <u>overhauled</u>	Hawsers and Warps <u>the water</u>
Wales <u>Do</u>	Copper <u>none</u>	Standing & Running Rigging <u>Sufficient</u>
Plank (Bottom) and Counter <u>doubled 1841</u>		

General Observations and Opinion,

This Vessel is in very efficient Condition fit for the safe conveyance of dry and perishable Cargoes and may be classed

The Amount of Fee.....£ 1 : — is received by me A. 1

Certificate (if required) : 10/

Committee's Minute 28<sup>th</sup> Jan'y 1848

Character assigned Special B 2



© 2019

Lloyd's Register Foundation

Lon 1624-0173