

REPORT of SURVEY for REPAIRS.

No. 657 Survey held at London Date Jan^y 1 to 26 1840
 on the B^e Mayflower Master Conard
 Tonnage 32 1/2 Built at Sunderland When built 1834
 By whom built _____ Owners H. Barrick
 Port belonging to London Destined Voyage Mediterranean
 If Surveyed Afloat or in Dry Dock In Duke Street Dock

Last Survey, No. 13279 Classed 10A⁺ 1
 Port London Cont 44. 3. 3 mo 4/

REPAIRS at the present time with a view to raise Class to 10A⁺
 The outside Planking from Yellow Metal Sheathing upwards secured
 with Treennails and Iron Bolts driven out at various parts for
 examination, a Plank of Bottom in Larb^d Buttock replaced with
 new, one Breast Hook in Hold repaired a few Treennails which were
 decayed renewed.

The Deck, Coamings, Deck and Hold Beam Bolts inside and
 outside Planking, Treennails, Planks her Waterway, Beams, knees,
 Breast-hooks, Knight heads, House Timbers, Keel, Keelson, Transoms,
 Floors and Timbers of the Frame when they may be seen, have been
 examined by us and are in good condition; her Stern appears to be in good
 condition.

Present Condition of the

Decks	Treennails	Windlass and Capstan
Waterways } <u>good</u>	Breasthooks and Stemson } <u>good when seen</u>	Pumps
Comings } <u>good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order and</u>
Lower Deck Beams & Fastenings <u>within view</u>	Keelsons <u>d^o</u>	Sails <u>Sufficient</u>
Planksheers <u>d^o</u>	Clamps and Shells <u>d^o</u>	Anchors No. of <u>2, 4, 11</u>
Sheerstrakes <u>d^o</u>	Ceiling <u>d^o</u>	Cables
Topsides <u>d^o</u>	Rudder <u>d^o</u>	Hawsers and Warps
Wales <u>d^o</u>	Copper Metal <u>d^o</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>d^o</u>		

General Observations and Opinion.

This Barque is now in good condition fit for the safe
 conveyance of dry and perishable Cargoes to and from all parts
 of the world, she has been specially surveyed by us in accordance
 with Rule Section 54. 60 and is recommended to be raised to 10A⁺

The Amount of Fee.....£..... is received by me.

Certificate (if required) : :

Committee's Minute 28th Jan^y 1840

Character assigned A-1

Special Fee £ 3. 3. - H. L.



© 2019

Lloyd's Register
 Foundation
 LON 624-0175