

ANNUAL SURVEYS.

14076

No. 262 on the *Volusia* Survey held at *London* Date *Feb March 1* 184*9*
 Tonnage *450* Built at *Worthing* Master *Finlayson*
 By whom built *Plotcher* Owners *Plotcher*
 Port belonging to *London* Destined Voyage *Honduras*
 If Surveyed Afloat or in Dry Dock *In Mess Plotcher's Dry Dock, lastly W.S. Day*

Last Survey, No. *12632* Port of *London* Classed *A 1*
46

The present Condition of the

Decks <i>part new sheathing and fitted</i>	Treenails	Windlass and Capstan
Waterways <i>good full class</i>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches <i>good full class where seen</i>	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <i>In good order and</i>
Lower Deck Beams & Fastenings <i>as before seen</i>	Keelsons <i>d^o</i>	Sails <i>sufficient</i>
Plank sheers	Clamps and Shelves <i>d^o</i>	Anchors No. of <i>3, 11 K 2</i>
Sheerstrakes <i>d^o</i>	Ceiling <i>d^o</i>	Cables
Topsides <i>d^o</i>	Rudder <i>d^o</i>	Hawsers and Warps
Wales <i>d^o</i>	Copper <i>Pyritab 44 d^o</i>	Standing & Running Rigging
Plank (Bottom) and Counter <i>F.S.S. 44</i>		

General Observations and Opinion,

Now done. A Shelf Piece of American Elm introduced under Hold Beams 12" square extending from abeam of Fore to Main Mast and thro' Bolted with Iron at about alternate Timbers. Yellow Metal sheathing repaired and the Deck Wood sheathed upon Pett from Stern to Fore part of Fore Hatchway.

Committee Minute *2nd March 1849*
 Character assigned *A 1*
Classed A 1
Ja S Martin
 Certificate (if required)

No. 363 on the *Elizabeth* Survey held at *London* Date *Feb 10 & Mar 1* 184*9*
 Tonnage *451* Built at *Greenock* Master *Alexander*
 By whom built *Hamlin* Owners *Hamlin*
 Port belonging to *Greenock* Destined Voyage *Madras*
 If Surveyed Afloat or in Dry Dock *In Snook's Dry Dock, lastly West India Dock*

Last Survey, No. *12244* Port of *London* Classed *10 A 1*
46

The present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways <i>good</i>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches <i>good where seen</i>	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <i>In good order and</i>
Lower Deck Beams & Fastenings <i>as before seen</i>	Keelsons <i>d^o</i>	Sails <i>sufficient</i>
Plank sheers	Clamps and Shelves <i>d^o</i>	Anchors No. of <i>3, 11 K 2</i>
Sheerstrakes <i>d^o</i>	Ceiling <i>d^o</i>	Cables
Topsides <i>d^o</i>	Rudder <i>d^o</i>	Hawsers and Warps
Wales <i>F.S.S. 46 d^o</i>	Copper <i>Yellow Metal now new upon Paper</i>	Standing & Running Rigging
Plank (Bottom) and Counter <i>d^o</i>		

General Observations and Opinion,

Now done. The Yellow Metal Sheathing stripped off and renewed. Bottom, Seams of Deck next the Waterway and around Stanchions, Caulked.

Committee Minute *3rd March 1849*
 Character assigned *10 A 1*
Classed A 1
Ja S Martin
 Certificate (if required)