

14088

REPORT of SURVEY for REPAIRS.

Change of Owners

No. 338 Survey held at London Date 24th 25 Feb 1848
on the Argentine "Alfred" Master _____
Tonnage 135 Built at Alloa When built 1819
By whom built _____ Owners Madder & Co
Port belonging to Colchester Destined Voyage _____
If Surveyed Afloat or in Dry Dock on Four Raft ways

Last Survey, No. 768 Classed _____
Port Stockton Npt 584 Lon 13760

REPAIRS at Present a new twist deck breasthook of English oak fitted, part new upper deck forward on the starboard side - has lately had a new upper deck beam abaft the Windlass and one ^{hole} before the main Mast - This is the third survey which the Owners have called and each time we have pointed out to them the very defective state of the hole ceiling and clamps and lower deck spunketting and also of the trenails below the wales - and the necessity of repairing these parts of the vessel she has again suited with the avowed intention of doing the necessary repairs at Middleboro

Present Condition of the			
Decks	<u>Repaired</u> <u>Good</u>	Trenails	<u>defective</u> <u>with</u> <u>timber</u>
Waterways	<u>Good</u>	Breasthooks and Stemson	<u>all new</u>
Comings	<u>Good</u>	Transoms, Pointers, and Crutches	<u>Good</u>
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>where sea supply</u>
Lower Deck Beams & Fastenings	<u>Good</u>	Keelsons	<u>Good</u>
Planksheers	<u>Good</u>	Clamps and Shelves	<u>whole defective</u>
Sheerstrakes	<u>Good</u>	Ceiling	<u>in hole very defective</u>
Topsides	<u>Good</u>	Rudder	<u>Good</u>
Wales	<u>Good</u>	Plank (Bottom) and Counter	<u>requires caulking</u>
General Observations and Opinion,			<u>Yacht on full</u>

until this vessel is properly repaired she should remain without character

Joseph H. Ritchie
Augustine Grey

The Amount of Fee.....£ 10 : - is received by me,

Certificate (if required) _____

Committee's Minute 7th March 1848

Character assigned Repaired
Special Survey 22