

14243

REPORT of SURVEY for REPAIRS.

No. 169 Survey held at London Date 22 & 24th Oct 1848
on the Ten-Elbe Packet Master Croft
Tonnage 141 Built at Little Hampton When built 1826
By whom built Williams Owners Williams
Port belonging to London Destined Voyage
If Surveyed Afloat or in Dry Dock on Wetts Ways

Last Survey, No. 376 Classed 10 R. 1
Port Gloucester 1838 Ret. 7 A 1

REPAIRS at Present 4 planks in larboard buttocks & run
shifted timbers exposed sound but Carefully shifted
2 after hoods on the Starboard side new. a new
iron cratch fitted to the keels of after Cant timber
thru' bolted with iron - an anchor stock piece fitted
in the fore Scupph of Kelson and a new Hog Kelson
34 ft long 12 x 8 fitted over extending below the tops
of both Masts - Rudder snatched new back piece
and rudder bands refitted - Wales topsides and
sheerstrakes scraped bright and bolts and turned
driven out for survey and found good Many turned
over hauled and renewed

Decks	Good	Treenails	Overhauled -	Windlass and Capstan	Good
Waterways	—	Breasthooks and Stemson	Good	Pumps	Lead —
Comings	—	Transoms, Pointers, and Crutches	new one fitted	Boats	two
Upper Deck Beams & Fastenings	—	Timbers of the Frame	Sound	Masts, Yards, &c.	Sufficient
Lower Deck Beams & Fastenings	—	Keelsons	new hog kelson sound / good	Sails	2 sets
Planksheers	Scraped bright good	Clamps and Shelves	Good	Anchors No. of	2. 1. 1
Sheerstrakes		Ceiling	—	Cables	— 2
Topsides		Rudder	new back piece and bands refitted	Hawsers and Warps	three
Wales	Calked	Copper	None	Standing & Running Rigging	good
Plank (Bottom) and Counter	—				

General Observations and Opinion, of
The Requirements of the Rules Sect 54 & 60
having been complied with and being in efficient
Condition and fit for the safe conveyance of dry
and perishable Cargoes to & from all Ports

The Amount of Fee £ : 10 : — is received by me, W. H. H. H.
Certificate (if required) : W. H. H. H.
Committee's Minute 2nd May 1848
Character assigned 1st Class
Lloyd's Register Foundation