

Restoration 1433

REPORT of SURVEY for REPAIRS.

No. 130 Survey held at London Date May & June 1848
 on the Sch "Isabel" Master R. Medhurst
 Tonnage 153 Built at Hastings When built 1831
 By whom built Ransom Owners J & J Adam
 Port belonging to London Destined Voyage Bayroute
 If Surveyed Afloat or in Dry Dock Mountain Dock

Last Survey, No. 1310 Classed 12 R, N
 Port London C 4

REPAIRS 1848 She has been Surveyed in Conformity with the
 Society's Rules Section 36. The waterways, plank sheers, new
 Strakes, part of the wales, the strake of the upper course
 of the bottom and a plank at the floorboards new
 taken out and the bottom stripped.

Repairs 10 whole top timbers 45 filling timbers
 26 long & 100 timbers 2 side counter timbers 4 new
 stern timbers (scupper) 3 new upper deck beams, new sheer
 strakes, topsides, part new wales, new waterways (Red Pine) new
 new strake in upper course of bottom, all new upper deck
 fastenings all of high class materials. English Oak & E. S. Teak
 Present Condition of the

Decks <u>new 1848</u>	Treenails <u>Very good</u>	Windlass and Capstan <u>good</u>
Waterways <u>new Solid Red Pine 1848</u>	Breasthooks and Stenson <u>good</u>	Pumps <u>do</u>
Comings <u>good</u>	Transoms, Pointers, and Crutches <u>do</u>	Boats <u>efficient</u>
Upper Deck Beams & Fastenings <u>new</u>	Timbers of the Frame <u>Very good</u>	Masts, Yards, &c. <u>do</u>
Lower Deck Beams & Fastenings <u>do</u>	Keelsons <u>do do</u>	Sails <u>do</u>
Plank sheers <u>new English Oak</u>	Clamps and Shelves <u>do do</u>	Anchors No. of <u>2 B 15' 1K efficient</u>
Sheerstrakes <u>new English Oak</u>	Ceiling <u>do do</u>	Cables <u>do</u>
Topsides <u>part new E. S. Teak</u>	Rudder <u>do do</u>	Hawsers and Warps <u>do</u>
Wales <u>part new</u>	Copper <u>gunn Metal 1848</u>	Standing & Running Rigging <u>do</u>
Plank (Bottom) and Counter <u>good</u>		

General Observations and Opinion, She has been Surveyed in Conformity with the
Society's Rules and received the above repairs in other parts
Is in the best sound & efficient state and may be
Restored & A1

The Amount of Fee.....£ 2 is received by me, J. Fortney
A. H. H. H.

Certificate (if required) _____
 Committee's Minute 16th June 1848
 Character assigned Restored A1