

REPORT of SURVEY for REPAIRS.

Continuation

No. 242 Survey held at London Date Sept 7 1848
on the Schooner "Viza" Master E. Torve
Tonnage 120 Built at Lynnington When built 1830
By whom built Owners Capt. & Co.
Port belonging to Southampton Destined Voyage Mediterranean
If Surveyed Afloat or in Dry Dock Afloat & lastly on Fire & aft. Ways

Last Survey, No. 379 Port Portsmouth Classed 10 A 1 46

REPAIRS

Now done in conformity with Rule for Continuation Sec 54

The Outside Planking from Copper upwards scraped bright Treenails and Iron Bolts driven through for examination at various parts.

An additional Breast hook of Iron introduced below and this Bolted with Copper; a new piece of False Keel in Midship. about 2 dozen Sheets expended in repainting Copper

The Deck, Coamings, Deck Bolts, Inside and Outside Planking, Treenails, Planks her, Waterway, Beams, Knees, Breast hooks, Knight-heads, House Timbers, Transoms, Keel, Keelson, Floors and Timbers of the Frame where they may be seen have been examined by us and are in good condition. The original Turn appears to be preserved

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } good	Breasthooks and Stems	Pumps
Comings } good when seen	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. In good order
Lower Deck Beams & Fastenings } dentures seen	Keelsons d ^o	Sails and sufficient
Planksheers	Clamps and Shelves d ^o	Anchors No. of
Sheerstrakes d ^o	Ceiling d ^o	Cables
Topsides d ^o	Rudder d ^o	Hawsers and Warps
Wales d ^o	Copper d ^o When put on 1846	Standing & Running Rigging
Plank (Bottom) and Counter d ^o		

General Observations and Opinion,

This Schooner has now been specially surveyed by us in accordance with Rule for Continuation Sec 54 and we are of opinion that she is in good condition eligible to be continued A 1 for 3 years from 1848

The Amount of Fee.....£ 1 : - : - is received by me.

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 12th Sept. 1848

Character assigned Oct 31 1848

Special Fee £