

14758

REPORT of SURVEY for REPAIRS.

No. 58 Survey held at London Date Nov^r 16th to 27th 1848
on the Sc^r "Gem" Master A Hannah
Tonnage 110 Built at Bridport When built 1837
By whom built _____ Owners Spright & Co
Port belonging to Limerick Destined Voyage Mediterranean
If Surveyed Afloat or in Dry Dock Dry on Crisp & Sons Ways

Last Survey, No. 12771 Port London Classed 11 A 1
46

REPAIRS at the present time in complying with Special Survey for
Continuation Rule Section 54

The Outside Planking from light water mark upwards scaped
bright Treennails and Iron Bolts driven out at various parts for
examination, two Hold Beams replaced with new, Caulked
Outside above Yellow Metal Sheathing and all Treennails ^{tried} about
350 of them on each side renewed: a broken Iron Hanging
Knee to Deck Beam repaired and refitted, a Crutch or Hook
of Iron added across lower Transoms, and this bolted with
Copper, she having no Pointers; a few Graving Pieces in Sheer Strake.

The Deck, Coamings, Deck, and Hold Beam Bolts, Inside and outside
Planking, Treennails, Plank sheer, Watertway, Beams, Knees, Breast hooks, Knee
heads, Plank Timbers, Transoms, Keel, Keelson Floors and Timbers of the Frame
where they may be seen have been examined by us and are in good condition, the
Present Condition of the original Form appears to be preserved

Decks	Treennails	Windlass and Capstan
Waterways	<u>good</u>	Pumps
Comings	Breasthooks and Stemson	Boats
Upper Deck Beams & Fastenings	Transoms, Pointers, and Crutches	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Timbers of the Frame	Sails
Plank sheers	Keelsons	Anchors No. of
Sheerstrakes	Clamps and Shelves	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	Copper <u>Metal</u> When put on <u>1846</u>	

General Observations and Opinion,

This Schooner has now been Specially Surveyed
by us in accordance with Rule for Continuation Section 54
and we are of opinion that she is in good condition eligible to
be continued A1 for 4 years

The Amount of Fee.....£ 2 : -

is received by me.

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 1st Dec^r 1848

Character assigned A1

Special Fee on
Continuation



© 2019

Lloyd's Register
Foundation

LON 625-0456