

REPORT of SURVEY for REPAIRS.

No. 680 Survey held at London Date 25 Oct till 22 Nov 1848
 on the Bark "Medora" Master F. Silk
 Tonnage 235 Built at Bristol When built 1825
 By whom built _____ Owners Shepherd & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock in Messrs Youngs Dock & West End in D

Last Survey, No. 13036 Port London Classed 102
1843/Rest of 1848

REPAIRS at Present from Damage break of quarter deck strengthened by diagonal bracing upon knees refastened & new breast work fitted damages on deck and to joiner work repaired - bottom stripped treenails renewed from the upper Courses to the first futtock heads on both sides - hung in shores Caulked from the keel up over the decks - Keel seams and Scarph hooding ends and butts of bottom listed with yellow Metal on pitch - Ceiling repaired two tadder braces off & refitted throat bolts of some of the hold beam knees renewed - Hull generally overhauled -

Present Condition of the

Decks <u>Caulked Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>---</u>	Breasthooks and Stemson <u>---</u>	Pumps <u>belly pumps repaired</u>
Comings <u>---</u>	Transoms, Pointers, and Crutches <u>---</u>	Boats <u>buys coat</u>
Upper Deck Beams & Fastenings <u>Some throat bolts partly</u>	Timbers of the Frame <u>---</u>	Masts, Yards, &c. <u>dr</u>
Lower Deck Beams & Fastenings <u>---</u>	Keelsons <u>---</u>	Sails <u>dr</u>
Plank sheers <u>Caulked Good</u>	Clamps and Shells <u>---</u>	Anchors No. of <u>dr</u>
Sheerstrakes <u>---</u>	Ceiling <u>repaired</u>	Cables <u>dr</u>
Topsides <u>---</u>	Rudder <u>over hauled</u>	Hawsers and Warps <u>dr</u>
Wales <u>---</u>	Copper <u>Y Metal</u> When put on <u>pitch</u>	Standing & Running Rigging <u>dr</u>
Plank (Bottom) and Counter <u>---</u>		

General Observations and Opinion,

This vessel is in efficient Condition and may remain as Classed

The Amount of Fee.....£ 1 : 0 : 0 is received by me,

Special..... 3 : 3 : 0

Certificate (if required) ---

Committee's Minute 5th Jan 1849

Character assigned Rest of 1848

Special Damage £3.3 - ---



© 2019

Lloyd's Register Foundation

LON626-0046