

REPORT of SURVEY for REPAIRS.

Damage & Relapsing

No. 178

Survey held at

London

from

Date 9 Dec 1848 till 10 Jan 1849

on the

Bark "Hector"

Master

M Brooks

Tonnage

293

Built at

Bristol

When built

1824

By whom built

Owners

Shepherd

Port belonging to

London

Destined Voyage

Jamaica

If Surveyed Afloat or in Dry Dock

in Mr Kings Dock & West India Docks

Last Survey, No.

13497

Port

London

Classed

A. 1

REPAIRS

at present from damage - bottom stripped of Wood and Copper Sheathing - and new fore piece of Main Keel and all new 5 inch false Keel four new Cross Chocks fitted forward with new fore woods of hold Ceiling new hog Keelson forward one new hold beam before the Main hatchway - hung in Shores. Caulked to the hold bottom Keels with wood on felt & yellow Metal to the wales - 3 new Rudder bands fitted -

and not from damage one additional hold beam fitted Ceiling repaired above the bilges one Strake new deck on one side Many bolts of lower deck binding renewed - wales topsides and Sheerstrakes Scraped from Copper up to mainmast driven out for survey found good bolts where defective renewed - the outside and Ceiling Planks the water

Present Condition of the

Decks

New 41 & 46 Good

Treenails

overhauled in hold Good

Windlass and Capstan

Good

Waterways

Good

Breasthooks and Stemson

Good

Pumps

Comings

Transoms, Pointers, and Crutches

Boats

Upper Deck Beams & Fastenings

in hold bolts renewed

Timbers of the Frame

Masts, Yards, &c.

Sufficient

Lower Deck Beams & Fastenings

in hold bolts renewed

Keelsons

New hog forward

Sails

Better

Planksheers

Sheerstrakes

Scraped

Clamps and Shelves

Good

Anchors

No. of

3 1 1

Topsides

bright

Ceiling

repaired

Cables

Sufficient

Wales

Good

Rudder

Good

Hawsers and Warps

D

Plank (Bottom) and Counter

fairly doubtful

Copper

Y Metal When put on new

Standing & Running Rigging

D

General Observations and Opinion,

This Vessel is now in efficient Condition and appears fit for the safe conveyance of dry and perishable Cargoes to & from all parts of the world and may be Classed A. 1 with Master

The Amount of Fee.....£ 1 : : is received by me,

Special..... 3 : 3 : -

Certificate (if required)

Committee's Minute

19th Jan 1849

Character assigned

A. 1 - Shear

Special Damage £ 4 4 - 0

7400-929207

14878. *For*

The waterways, and beams the knee timbers, Ruythunders
breasthooks & transoms the floors & keelsons and the floor
and inner surface of the outside planking where seen
are sound & good and the sheer & general form appear
unaltered —

S. A. Ritchie



© 2019

Lloyd's Register
Foundation