

REPORT of SURVEY for REPAIRS.

No. 227 Survey held at Sondou Date 19 Jan till 9 Mar 1849
 on the Ship "Simandra" Master R E Wicks
 Tonnage 382 Built at Little Hampton When built 1841
 By whom built _____ Owners F Castelle
 Port belonging to Sondou Destined Voyage Havannah
 If Surveyed Afloat or in Dry Dock in West India Dock & Globe Dock

Last Survey, No. 13373 Port Sondou Classed 11 A 1

REPAIRS at present from damage all new Kougteen Stanchions and Rails on Main Deck and on quarter deck and all new bulwarks - New after hatch Comings New Main Piece of Tadder bottom Stripped, hung, Caulked and Treeshoed with yellow Mahoe all new Masts and Spars except fore Mast (which has been fished) the bowsprit head rails & timbers & berthing refitted - And not from damage the Poop removed and upper deck cut and beams dropped down and new quarter deck formed 3' 6" above the line of upper deck but 6 feet shorter than old Poop New quarter deck sheer strakes and berthing and Clamps, Plan Sheer and Ceiling of long lengths of English oak Plank of good quality and sufficient present Condition of the Keel - New front and after beam of quarter deck

Decks <u>all new quarter deck</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>new quarter deck</u>	Breasthooks and Stemson <u>---</u>	Pumps <u>new main & bilge pumps</u>
Comings <u>refitted</u>	Transoms, Pointers, and Crutches <u>---</u>	Boats <u>two new</u>
Upper Deck Beams & Fastenings <u>all new aft</u>	Timbers of the Frame <u>---</u>	Masts, Yards, &c. <u>partly new & rest good</u>
Lower Deck Beams & Fastenings <u>---</u>	Keelsons <u>---</u>	Sails <u>many new</u>
Plank sheers <u>quarter deck new</u>	Clamps and Shelves <u>---</u>	Anchors No. of <u>3</u>
Sheerstrakes <u>quarter deck new</u>	Ceiling <u>---</u>	Cables <u>sufficient</u>
Topsides <u>Good</u>	Rudder <u>new main piece</u>	Hawsers and Warps <u>new in part nearly all</u>
Wales <u>---</u>	Copper <u>new</u> When put on <u>March 1849</u>	Standing & Running Rigging <u>new</u>
Plank (Bottom) and Counter <u>---</u>		

General Observations and Opinion,

This Vessel is in now in most efficient Condition and may remain as Clipped

The Amount of Fee.....£ 2 : : is received by me,

Special..... 5 : 5 : -

Certificate (if required) : 10 : -

Committee's Minute 30th March 1849

Character assigned 11 A 1

Special Damage £ 5.5



© 2019

Lloyd's Register Foundation

LON626-0251

1505^B Jan -

and old beams refitted of Main deck on new English oak
shelf - all new quarter deck Plank new Counter beam
with knees at each end - New breast bulkhead and be
tail of quarter deck. Entirely new Cabin fitting and
work - Chulked all over. New long boats & quarter boat
furnished and many new sails and new lower rigging
all the masts and new topmast rigging & stays and lower
rigging to main & mizen masts - Hull, generally
overhauled and refitted -

St. Kitts

Fort May



© 2019

Lloyd's Register
Foundation