

REPORT of SURVEY for REPAIRS.

Restoration 15209

No. 453 Survey held at London Date April 24 27 28
May 25 1849
 on the City of London Master J. W. Bull
 Tonnage 330 Built at Luth When built 1834
 By whom built 395 Owners James H. H.
 Port belonging to London Destined Voyage Ceylon
 If Surveyed Afloat or in Dry Dock James H. H.

Last Survey, No. 12378 Port London Classed B A 1

REPAIRS

At the present time the water ways, plank sheers, sheer strakes
 topsides Black Strakes all taken down, and two strakes of the wales and
 stake of upper course of Bottom taken out in conformity with the
 Society's Rules for Restoration

New main beam 2 New Side counter timbers about 80 new short
 and long top timbers 2 new strakes of wales cabash sides and new
 new planks in ditto African Oak & I Teak, and new strake in
 upper course of Bottom and several new planks in the battens etc
 new Black Strakes topsides sheer strakes sheer strakes and
 plank sheers of Mahogany & I Teak & African, new water ways
 Red pine, new strake of deck next water way, new upper deck
 beam and one half ditto part new Lathing to top gallop
 free bottom

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of 3 B/SIK
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper	Standing & Running Rigging
Plank (Bottom) and Counter	When put on	

General Observations and Opinion,

She has been repaired in the most efficient
 manner and may in our opinion be ~~restored~~ classed
 B A 1 from this date —

The Amount of Fee.....£ 4 : — : — is received by me,

Special..... 10 : 10 : —

Certificate (if required) : 10 : —

Committee's Minute 8th June 1849

Character assigned Restored



© 2019

Lloyd's Register
 Foundation

LON626-0406

15209 Lon

New poop timbers bulking sheer strake & Watway to poop
part New Ceiling New Keelson of S. I. Deck bottom partly
new nunnit all new bolts to the knees & shelves of both decks
a pair of long iron riders in the after body, new Rudder
the high quarter deck raised and made a poop, & properly
seamed, - Caulked from the Keel up over ~~head~~ all that had
with yellow Metal upon fett new bolts in the breast Hooks

Forbury
J. St. John



© 2019

Lloyd's Register
Foundation