

15246

## REPORT of SURVEY for REPAIRS.

Change of Owners

No. 1 Survey held at London Date 14<sup>th</sup> 15<sup>th</sup> 21<sup>st</sup> June 1849  
 on the Bk Constant Master J. J. Coombes  
 Tonnage 445 Built at Nycton When built 1842  
 By whom built                      Owners R & R Towner  
 Port belonging to London Destined Voyage                       
 If Surveyed Afloat or in Dry Dock in Limekiln Dock

Last Survey, No. 13337 Port London Classed GA 1

## REPAIRS

at Present bottom stripped away in shows entirely  
 new Keelson fitted of East India Teak in two lengths  
 thro bolted with 1 1/4 yellow Metal. New 4" false Keel fitted  
 New Main piece of rudder also fitted. Caulked to the  
 wales and bottom sheathed with yellow Metal. on  
 Canvas - New Stemson Rudder <sup>ftg</sup> lower breasthook  
 Renewed of iron

## Present Condition of the

Decks	Treenails	Overhauls
Waterways	Breasthooks and Stemson	Windlass and Capstan <u>Good</u>
Comings	Transoms, Pointers, and Crutches	Pumps <u>                    </u>
Upper Deck Beams & Fastenings	Timbers of the Frame	Boats <u>Three</u>
Lower Deck Beams & Fastenings	Keelsons <u>all new</u>	Masts, Yards, &c. <u>Sufficient</u>
Plank sheers	Clamps and Shelves	Sails <u>                    </u>
Sheerstrakes	Ceiling	Anchors No. of <u>3</u> <u>1</u> <u>1</u>
Topsides	Rudder <u>new main</u>	Cables <u>Sufficient</u>
Wales	Gaffer <u>Ym</u> When put on <u>June 1849</u>	Hawsers and Warps <u>                    </u>
Plank (Bottom) and Counter		Standing & Running Rigging <u>Good</u>

## General Observations and Opinion,

This Vessel is now in efficient Condition  
and may remain as classed  
J. J. Coombes

The Amount of Fee.....£ 2 : : is received by me,

Special..... 1 : 1 : -

Certificate (if required)                     

Committee's Minute 24<sup>th</sup> June 1849

Character assigned                     

Special £ 1. 1. -



© 2019

Lloyd's Register  
 Foundation