

# REPORT of SURVEY for REPAIRS.

15365

No. 10 Survey held at London Date July 24<sup>th</sup> 1849  
 on the Barque "Cairo" Master Hogg  
 Tonnage 300 Built at Dundee When built 1839  
 By whom built \_\_\_\_\_ Owners Jas. J. Shepherd  
 Port belonging to London Destined Voyage Jamaica  
 If Surveyed Afloat or in Dry Dock In Mess<sup>r</sup> Young Son & Co Dry Dock

Re. 27 July

Last Survey, No. 14,325 Port London Classed 9 1  
40

## REPAIRS

Now done in conformity with Special Survey Rule for Continuation Section No 54. The Outside Planking from lower part of Wales upwards scraped bright Treenails and Iron Bolts driven out at various parts for examination, Yellow Metal Sheathing stripped off and renewed upon Paper, Ship hung in Shous, Bottom Caulked, a few pieces inserted in Planking of Buttocks, and the Aftermost piece of Keelson new.

The Deck, Coamings, Deck and Hold Beam Bolts inside and Outside planking, Treenails, Planksheer, Waterway, Beams, Knees, Breast hooks, Knight heads, Hamsetimber, Transoms, Keelson Keel, Floors and Timbers of the Frame where they may be seen have been examined by us and are in good condition. Her original Form appears to be preserved

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>good</u>	Breasthooks and Stemson } <u>good where seen</u>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order</u>
Lower Deck Beams & Fastenings } <u>d<sup>r</sup> where seen</u>	Keelsons <u>d<sup>r</sup></u>	Sails <u>and sufficient</u>
Planksheers	Clamps and Shelves <u>d<sup>r</sup></u>	Anchors No. of
Sheerstrakes <u>d<sup>r</sup></u>	Ceiling <u>d<sup>r</sup></u>	Cables
Topsides <u>d<sup>r</sup></u>	Rudder <u>d<sup>r</sup></u>	Hawsers and Warps
Wales <u>d<sup>r</sup></u>	Copper <u>Yellow Metal</u> When put on <u>now new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>d<sup>r</sup></u>	<u>upon paper</u>	

General Observations and Opinion,

This Barque has now been Specially Surveyed by us in accordance with Rule for Continuation and we are of opinion that she is in good condition eligible to be continued 1

The Amount of Fee.....£ 4 : 0 : 0 is received by me, for 3 years from 1848

Special.....£ 3 : 3 : 0

Certificate (if required) : :

Committee's Minute 14 Aug 1848

Character assigned Car P D 1 for 3 yrs

Special Continuation d<sup>r</sup> 1848 - continued

© 2019 Lloyd's Register Foundation

LON627-0087