

REPORT of SURVEY for REPAIRS.

15421

No. 539 on the *B¹⁶ "Collingwood"* Survey held at *London* Date *July 9th Aug 9th* 1849
 Master *J. Morrison*
 Tonnage *637* Built at *Sunderland* When built *1847*
 By whom built _____ Owners *J. Dunbar*
 Port belonging to *London* Destined Voyage *Calcutta*
 If Surveyed Afloat or in Dry Dock *In Shooks Dry Dock, and lastly Port India Dock*

Last Survey, No. *13475* Port *London* Classed *10 A 1*

REPAIRS of damage done at Calcutta by reason of a Hurricane off the Sand Head near Calcutta in her outward passage.

Fore and Main Masts, Bowspit, all Masts, Yards, Sails and Rigging thereto belonging new, also the Boats, except Long Boat: Yellow Metal Sheathing stripped off Caulked throughout and the Bottom Sheathed with ~~Yellow Metal~~ Copper upon Chumam: five pairs of Iron Standard Knees upon Lower Deck Beams and five pairs of Iron Knee Riders added in Hold extending across Floor Heads the latter thro' Bolted with Copper: all the Outside Planking from Gunwale downwards, extending lengthwise from Fore to Mizzen Mast extra Bolted thro' and Clinched with Iron Aloft and Copper below: the Upper and Lower Deck Fastening Bolts are reported to have been renewed in the same space.

Present Condition of the

Now done. Caulked outside above the Copper

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of <i>4 1 1 2</i>
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper upon Chumam	Standing & Running Rigging
Plank (Bottom) and Counter	When put on at Calcutta in Dec ^r 1840	

General Observations and Opinion,

The Damage above named appears to have been efficiently repaired at Calcutta, and she appears eligible to remain as Classed A 1

The Amount of Fee.....£ : : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute *7th Sept 1844*

Character assigned *10 A 1*

LON627-0145