

REPORT of SURVEY for REPAIRS.

15458

No. 841 Survey held at London Date Sept 5th 12 1849
on the Barque "Asia" Master Roskell
Tonnage 523 Built at Calcutta When built 1815
By whom built 637 New Owners Hall & Co
Port belonging to London Destined Voyage Sydney
If Surveyed Afloat or in Dry Dock In Mess^r Wigram's Dry Dock

Last Survey, No. 13176 Port London Classed *R.1

REPAIRS At the present time of damage sustained by striking the ground also by a Hurricane in China, more particulars in Special Report
Ship hung in Shores Keel Seam, and Head ends Caulked; seven pairs of Iron Hanging Knees added to Upper Deck Beams, and one pair of Staple Standards, all this Bolted. She was Caulked above the Copper in China

Now done under Special Survey Rule Sec N^o 54. 60 with a view to reclassing *R.1. The Outside Planking from Y Metal Sheathing upwards, scraped tight. Iron Bolts driven out for examination and found good, the Yellow Metal Sheathing stripped off and renewed the Doubling from Wale to Keel Caulked, and the Hold Ceiling slightly repaired

The Deck, Coamings, Upper and Lower Deck Bolts, Inside and Outside Planking (the latter is Doubling) Planks here, Waterway, Beams, Knees, Hooks, Knight Heads, Hamse Timbers, Keel, Keelson, Floors and Timbers of the Frame where they may be seen have been examined by us and are in good condition
Present Condition of the

Decks	Greenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of <u>3, 1, 1, 2</u>
Sheerstrakes	Ceiling	Cables
Sides	Rudder	Hawsers and Warps
Wales	Copper Metal	Standing & Running Rigging
Plank (Bottom) and Counter	When put on <u>now new</u>	
	<u>upon bare Doubling</u>	

General Observations and Opinion,

This Barque has now been Specially Surveyed in accordance with Rule Sec N^o 54. 60 and we are of opinion that she is in good condition fit for the safe conveyance of

The Amount of Fee.....£ 3 : - : is received by me,
Special..... 3 : 3 : of the world eligible to be reclassified
Certificate (if required) : 10 : *R.1 and mark S.S 49

Committee's Minute 21st Sept 1849

Character assigned R.1 asterisk

Special Report &c on damage £ 14-14-0

By Jac S.S

J. S. Martin
R.1 asterisk
Record damage
£ 14-14-0
3-3-0
Wm. S. S.
Foundation

CON627-0182