

REPORT of SURVEY for REPAIRS.No.
886

on the

Survey held at

London

Date

Sept 19 to Oct 15 1849

Master

Waterson

Tonnage

492
579

Built at

London

When built

1811

By whom built

Owners

Heath & Co

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

In Messrs Wigram's Dry Dock

Last Survey, No.

14539

Port

London

Classed

* A. 1

40

REPAIRS

At the present time 70 feet Stanchion and 79 feet on the Port side of Upper Deck Clamp cut away, being decayed, the heads of Timbers at this part repaired by Fillings & and Filling Pieces fitted between the Hanging Knees home to their fronts, and a Shelf Piece introduced extending all Fore and Aft under Upper Deck Beams 9 by 12 of American Elm, Bolted up & down thro' each Beam end and Watertway, and thro' the sides, Bolts of Iron and Clinch at every two feet, one new Arm to each Beam, five new Arms to Lower deck Beams, the two Lower Breast Hooks repaired, and two Iron Breast Hooks added near them, 50 feet of Side Keelson introduced each side, 10 by 12 of Am Elm, thro' Bolted with Yellow Metal: The Yellow Metal Sheathing stripped off and renewed upon Felt, a Leak found in Keel Seam, and stopped, the Ship hung in Shaws, and Bottom Caulked, a new Upper Piece of Fore Stem, a new Piece of Head Cheeks and Rails

at Condition of the

| | | |
|--|---|---------------------------------|
| F&S 44 | Treenails | Windlass and Capstan |
| ways } good for Class recom | Breasthooks and Stemson | Pumps |
| gs } | Transoms, Pointers, and Clutches } good for Class | Boats |
| Deck Beams & Fastenings | Timbers of the Frame | Masts, Yards, &c. In good order |
| Deck Beams & Fastenings } d ^h | Keelsons d ^h | Sails and sufficient |
| sheers } | Clamps and Shelves d ^h | Anchors No. of |
| trakes } D 42 d ^h | Ceiling d ^h | Cables |
| les } | Rudder d ^h | Hawsers and Warps |
| F&D 37 d ^h | Copper Metal } When put on new new | Standing & Running Rigging |
| (Bottom) and Counter D 37 d ^h | upon Felt | |

Observations and Opinion,

The condition of the Top Timbers. Ceiling between the Planks here are such as not to entitle her to be recommended to retain the * character, of which the Owners are aware; She has been now much strengthened

Amount of Fee.....£ 2 : - : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : : :

Committee's Minute

11th Oct 1849

Character assigned

A. 1 omit asterisk record repairs

Special attendance £ 2-2-0

notice to owner

for 17 Oct

without the distinction of the *
J. A. Martin
Lloyd's Register
Foundation